

# LANCASTER COUNTY

COUNTY - CITY BUILDING Telephone: (402)441-7410  
LINCOLN, NEBRASKA 68508 FAX : (402) 441-6513  
*BOARD OF COMMISSIONERS*

IT IS THE VENDOR'S RESPONSIBILITY TO  
CHECK FOR ADDENDA PRIOR TO SUBMITTING PROPOSALS

## **NOTICE TO BIDDERS SPECIFICATION NO. 04-191**

Lancaster County intends to purchase and invites you to submit a sealed bid for:

### **REMOVE EXISTING ROOF AND INSTALL NEW ROOF AT 2966 "O" STREET**

#### **MEETING OR EXCEEDING THE LANCASTER COUNTY'S SPECIFICATIONS**

A pre-bid conference will be held at the site at 10:00 A.M., Tuesday, July 20, 2004. All bidders are encouraged to attend.

Sealed bids will be received by Lancaster County, Nebraska on or before **12:00 Noon Wednesday, July 28<sup>th</sup>, 2004** in the office of the Purchasing Agent, Suite 200, "K" Street Complex (SW Wing), located at 440 South 8th Street, Lincoln, Nebraska 68508. Bids will be publicly opened and read in the Bid/Conference Room located on the Ground Floor.

Bidders should take caution if U.S. Mail or mail delivery services are used for the submission of bids. Mailing should be made in sufficient time for bids to arrive in the Purchasing Division, prior to the time and date specified above. Late bids will not be considered.

Bidding documents may be examined at:

Lincoln Builder's Bureau, 5910 So. 58th St., Lincoln, NE 68516  
F.W. Dodge Corporation, 11422 Miracle Hills Drive, Omaha, NE 68144  
Omaha Builder's Exchange, 4255 So. 94th, Omaha, NE 68127  
Construction Marketing Data, 10665 Bedford Ave., #105, Omaha, NE 68127  
County-City Purchasing, County-City Bldg., 555 S. 10th St., Lincoln, NE 68508

---

#### **COMMISSIONERS**

*DEB SCHORR \* LARRY HUDKINS \* RAY STEVENS \* BERNIE HEIER \* BOB WORKMAN*  
KERRY EAGAN, Chief Administrative Officer

# SEALED BID

## SPECIFICATION NO. 04-191

BID OPENING TIME: 12:00 NOON  
DATE: Wednesday, July 28<sup>th</sup>, 2004

**ADDENDA RECEIPT:** The receipt of the addenda to the specification number \_\_\_\_ through \_\_\_\_ is hereby acknowledged. Failure of any bidder to receive any addenda or interpretation shall not relieve the bidder from obligations specified in the bid request. All addenda shall become part of the final contract document.

---

The undersigned submitter, having full knowledge of the requirements of Lancaster County for the above listed construction project, the Contract Documents and all other terms and conditions of the request, agrees to provide the labor, certificate of insurance, unemployment compensation, performance and payment bonds, materials and equipment in strict accordance with the plans and specifications as prepared by the County for the consideration of the amount set forth in the following price schedule:

### REMOVAL OF EXISTING ROOF AND INSTALLATION OF NEW ROOF AT 2966 "O" STREET

**1. To provide supervision, labor, materials, and equipment for work as indicated herein:**

**LUMP SUM OFFER - TOTAL PROJECT:** \$ \_\_\_\_\_

**Written:** \_\_\_\_\_

**Total number of consecutive calendar days to complete the project:** \_\_\_\_\_ Days

OPTION #1: Cost to replace with equal values and heights, any wet insulation.

SQUARE FOOT PRICE: \$ \_\_\_\_\_

OPTION #2: Cost to replace any bad metal decking.

SQUARE FOOT PRICE: \$ \_\_\_\_\_

**NOTE: A 5% Bidder's Bond is Required with your offer**

---

**NOTE: RETURN 2 COMPLETE COPIES OF BID OFFER AND SUPPORTING MATERIAL.  
MARK OUTSIDE OF BID ENVELOPE AS FOLLOWS: SEALED BID FOR SPEC. NO. 04-191**

---

The undersigned signatory of the bidder represents and warrants that he has full and complete authority to submit this offer to Lancaster County, and to enter into a contract if this offer is accepted.

\_\_\_\_\_  
COMPANY NAME

\_\_\_\_\_  
BY (Signature)

\_\_\_\_\_  
STREET ADDRESS or P.O. BOX

\_\_\_\_\_  
(Print Name)

\_\_\_\_\_  
CITY, STATE ZIP CODE

\_\_\_\_\_  
(Title)

\_\_\_\_\_  
TELEPHONE NO.

\_\_\_\_\_  
(Date)

\_\_\_\_\_  
FAX NO.

\_\_\_\_\_  
EMPLOYER'S FEDERAL I.D. NO.  
OR SOCIAL SECURITY NUMBER

Email: \_\_\_\_\_

BIDS MAY BE INSPECTED IN THE PURCHASING DIVISION DURING NORMAL BUSINESS HOURS, AFTER TABULATION. IF YOU DESIRE A COPY OF THE BID TABULATION TO BE MAILED TO YOU, YOU MUST ENCLOSE A SELF-ADDRESSED STAMPED ENVELOPE WITH YOUR BID. Bid tabulations can also be viewed on our website at: <http://www.ci.lincoln.ne.us/city/finance/purch/specindx.htm>

# **SUBMITTAL CHECKLIST AND DOCUMENTS**

## **FOR #04-191 REMOVE EXISTING ROOF & INSTALL NEW ROOF AT 2966 "O" STREET**

The following list is to serve as a guide for the required submittal information outlined in this specification. The items are defined in the Submittal Section, Qualifications of Bidders and manufacturers Qualifications Section under the **Instruction to Bidders**. Please carefully review these items and submit them to Mr. Don Killeen at 920 O S Street Lincoln, NE 68508, no later than five days before the bid due date.

1. Statement of Qualifications for Bidders
2. Statement of Roofing Manufacturer's Qualifications.
3. Specification Data Sheets to include manufacturer's technical product data, installation instructions, and recommendations for each type of roofing product required. Include data substantiating that materials comply with specified requirements.
4. Submit signed affidavit from manufacturer attesting to the validation of the Manufacturers Qualification Statement.
5. Submit signed and completed Bidders Qualification Statement as outlined in Qualification of Bidders.
6. Unexecuted Manufacturer's Warranty.

# STATEMENT OF QUALIFICATIONS OF BIDDERS

FOR #04-191

REMOVE EXISTING ROOF & INSTALL NEW ROOF  
AT 2966 "O" STREET

Each bidder for the work included in the specifications and drawings and the contract documents shall submit the data requested in the following schedule of information. This data must be included as noted in the Contractor's Qualification Section, under Instruction to Bidders. This form must be signed by an Officer or Partner of the Contractor's Business. Failure to comply with this instruction may be regarded as justification for rejecting the Contractor's Proposal. Submit one (1) copy of this statement with your prior approvals.

1. Name of Bidder \_\_\_\_\_
2. Permanent Place of Residence \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_
3. Number of years at this address \_\_\_\_\_
4. Submitted list of five references as outlined under Qualifications of Bidders \_\_\_\_\_
5. Has above Bidder or any current Officer or Partner of the Bidder, filed Chapter 7 in the last ten (10) years? \_\_\_\_\_
6. Submit current independent laboratory results on roofing system that is proposed, prior to award of contract.
7. I have read and understand the Submittals Section of this specification. I have included the required information for submittal as outlined in the specification. Initial for acceptance of statement \_\_\_\_\_.

I know that the above statements made are true.

Bidders name and address (printed):

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Signed \_\_\_\_\_

Title \_\_\_\_\_

Date: \_\_\_\_\_

# STATEMENT OF ROOFING MANUFACTURER'S QUALIFICATIONS

## FOR #04-191 REMOVE EXISTING ROOF & INSTALL NEW ROOF AT 2966 "O" STREET

Each bidder for the work included in the specifications and drawings and the contract documents shall submit the data requested in the following schedule of information. This data must be included as noted in the Manufacturers Qualifications Section, under Instructions to Bidders. A signed affidavit by a corporate officer of the Roofing Materials Manufacturer must accompany this Statement certifying the data's authenticity. Failure to comply with this instruction may be regarded as justification for rejecting the Contractor's Proposal. Submit one (1) copy of this statement with your prior approvals.

1. Name of bidder
2. Name of Material Supplier
3. Number of years manufacturing this roof system
4. Location of wholly owned and operated manufacturing facilities.

Facility \_\_\_\_\_ Facility \_\_\_\_\_

Product \_\_\_\_\_ Product \_\_\_\_\_

Street \_\_\_\_\_ Street \_\_\_\_\_

City \_\_\_\_\_ City \_\_\_\_\_

State \_\_\_\_\_ State \_\_\_\_\_

% of product used  
mfg at this plant \_\_\_\_\_

% of product used  
mfg at this plant \_\_\_\_\_

Facility \_\_\_\_\_ Facility \_\_\_\_\_

Product \_\_\_\_\_ Product \_\_\_\_\_

Street \_\_\_\_\_ Street \_\_\_\_\_

City \_\_\_\_\_ City \_\_\_\_\_

State \_\_\_\_\_ State \_\_\_\_\_

% of product used  
mfg at this plant \_\_\_\_\_

% of product used  
mfg at this plant \_\_\_\_\_

5. Submit ISO 9001 Certification Number \_\_\_\_\_, attach copy of ISO 9001 Certificate.
6. Submit current independent laboratory results on roofing system's ability to meet fire rating specified
7. Attached list of three jobs where proposed roof system has been used in similar roofing system, within 100 mile radius of project, and at least three years old.

# LANCASTER COUNTY

COUNTY - CITY BUILDING  
LINCOLN, NEBRASKA 68508  
BOARD OF COMMISSIONERS

Telephone: (402)441-7410  
FAX : (402) 441-6513

SAMPLE  
**CHANGE NOTICE**

CHANGE ID # \_\_\_\_\_

The following information must be completed and signed prior to any work being done which varies in any way from the Bidding Documents and Garland Specifications as submitted. Failure to properly complete this form shall void any subsequent requests for payments which may be made in addition to the submitted bidding documents.

Name of Account: \_\_\_\_\_

Project Name: \_\_\_\_\_

Project Number:     #04-191    

Name of Contractor: \_\_\_\_\_

Proposed Changes:

Amount Not To Exceed: \$ \_\_\_\_\_

Submitted By: \_\_\_\_\_ Title \_\_\_\_\_

Approved By: \_\_\_\_\_ Title \_\_\_\_\_

Date Approved: \_\_\_\_\_ / \_\_\_\_\_ / \_\_\_\_\_

Copy To:

- 1) Building Owner
- 2) Contractor
- 3) Garland Representative
- 4) Sub-Contractor

# **INSTRUCTIONS TO BIDDERS**

## **LANCASTER COUNTY, NEBRASKA PURCHASING DIVISION**

### **1. BIDDING PROCEDURE**

- 1.1 Bidder shall submit two (2) complete sets of the bid documents and all supporting material. All appropriate blanks shall be completed. Any interlineation, alteration or erasure on the specification document shall be initialed by the signer of the bid. Bidder shall not change the proposal form nor make additional stipulations on the specification document. Any amplified or qualifying information shall be on the bidder's letterhead and firmly attached to the specification document.
- 1.2 Bid prices shall be submitted on the Proposal Form included in the bid document.
- 1.3 Bidders may submit a bid on an "all or none" or "lump sum" basis, but should also submit a quotation on an item-by-item basis. Bidding documents shall be clearly marked indicating the kind of proposal being submitted.
- 1.4 Each bid must be legibly printed in ink or by typewriter, include the full name, business address, and telephone number of the bidder; and be signed in ink by the bidder.
- 1.5 A bid by a firm or organization other than a corporation must include the name and address of each member.
- 1.6 A bid by a corporation must be signed in the name of such corporation by a duly authorized official thereof.
- 1.7 Any person signing a bid for a firm, corporation, or other organization must show evidence of his authority so to bind such firm, corporation, or organization.
- 1.8 Bids received after the time and date established for receiving bids will be rejected.

### **2. BIDDER'S SECURITY**

- 2.1 Bid security, as a guarantee of good faith, in the form of a certified check, cashier's check, or bidder's bond, may be required to be submitted with this bid document, as indicated on the Proposal Form.
- 2.2 If alternate bids are submitted, only one bid security will be required, provided the bid security is based on the amount of the highest gross bid.
- 2.3 Such bid security will be returned to the unsuccessful bidders when the award of bid is made.
- 2.4 Bid security will be returned to the successful bidder(s) as follows:
  - 2.4.1 For single order bids with specified quantities: upon the delivery of all equipment or merchandise, and upon final acceptance by the County.
  - 2.4.2 For all other contracts: upon approval by the County of the executed contract and bonds.
- 2.5 County shall have the right to retain the bid security of bidders to whom an award is being considered until either:
  - 2.5.1 A contract has been executed and bonds have been furnished.
  - 2.5.2 The specified time has elapsed so that the bids may be withdrawn.
  - 2.5.3 All bids have been rejected.
- 2.6 Bid security will be forfeited to the County as full liquidated damages, but not as a penalty, for any of the following reasons, as pertains to this specification document:
  - 2.6.1 If the bidder fails to deliver the equipment or merchandise in full compliance with the accepted proposal and specifications.
  - 2.6.2 If the bidder fails or refuses to enter into a contract on forms provided by the County, and/or if the bidder fails to provide sufficient bonds or insurance within the time period as established in this specification document.

### **3. EQUAL OPPORTUNITY**

- 3.1 Each bidder agrees that it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, national origin, ancestry, disability, age, or marital status. Bidder shall fully comply with the provisions of Chapter 11.08 of the Lincoln Municipal Code.
- 3.2 Successful bidder will be required to comply with the provisions of the County's Affirmative Action Policy (Contract Compliance, Sec. 1.16).
- 3.3 The Equal Opportunity Officer will determine compliance or non-compliance with the County's Affirmative Action Policy upon a complete and substantial review of successful bidder's equal opportunity policies, procedures and practices.

**4. DATA PRIVACY**

- 4.1 Bidder agrees to abide by all applicable State and Federal laws and regulations concerning the handling and disclosure of private and confidential information concerning individuals and corporations as to inventions, copyrights, patents and patent rights.
- 4.2 The bidder agrees to hold the County harmless from any claims resulting from the bidder's unlawful disclosure or use of private or confidential information.

**5. BIDDER'S REPRESENTATION**

- 5.1 Each bidder by signing and submitting a bid, represents that the bidder has read and understands the specification documents, and the bid has been made in accordance therewith.
- 5.2 Each bidder for services further represents that the bidder is familiar with the local conditions under which the work is to be done and has correlated the observations with the requirements of the bid documents.

**6. INDEPENDENT PRICE DETERMINATION**

- 6.1 By signing and submitting this bid, the bidder certifies that the prices in this bid have been arrived at independently, without consultation, communication or agreement, for the purpose of restricting competition, as to any matter relating to such prices with any other bidder or with any competitor; unless otherwise required by law, the prices which have been quoted in this bid have not been knowingly disclosed by the bidder prior to bid opening directly or indirectly to any other bidder or to any competitor; no attempt has been made, or will be made, by the bidder to induce any person or firm to submit, or not to submit, a bid for the purpose of restricting competition.

**7. CLARIFICATION OF SPECIFICATION DOCUMENTS**

- 7.1 Bidders shall promptly notify the Purchasing Agent of any ambiguity, inconsistency or error which they may discover upon examination of the specification documents.
- 7.2 Bidders desiring clarification or interpretation of the specification documents shall make a written request which must reach the Purchasing Agent at least seven (7) calendar days prior to the date and time for receipt of bids.
- 7.3 Interpretations, corrections and changes made to the specification documents will be made by written addenda.
- 7.4 Oral interpretations or changes to the Specification Documents made in any other manner, will not be binding on the County; and bidders shall not rely upon such interpretations or changes.

**8. ADDENDA**

- 8.1 Addenda are written instruments issued by the County prior to the date for receipt of bids which modify or interpret the specification document by addition, deletion, clarification or correction.
- 8.2 Addenda will be mailed or delivered to all who are known by the County to have received a complete set of specification documents.
- 8.3 Copies of addenda will be made available for inspection at the office of the Purchasing Agent.
- 8.4 No addendum will be issued later than forty-eight (48) hours prior to the date and time for receipt of bids, except an addendum withdrawing the invitation to bid, or an addendum which includes postponement of the bid.
- 8.5 Bidders shall ascertain prior to submitting their bid that they have received all addenda issued, and they shall acknowledge receipt of addenda on the proposal form.

**9. ANTI-LOBBYING PROVISION**

- 9.1 During the period between the bid close date and the contract award, bidders, including their agents and representatives, shall not directly discuss or promote their bid with any member of the County Board or County Staff except in the course of County-sponsored inquiries, briefings, interviews, or presentations, unless requested by the County.

**10. BRAND NAMES**

- 10.1 Wherever in the specifications or proposal form brand names, manufacturer, trade name, or catalog numbers are specified, it is for the purpose of establishing a grade or quality of material only; and the term "or equal" is deemed to follow.



- 10.2 It is the bidder's responsibility to identify any alternate items offered in the bid, and prove to the satisfaction of the County that said item is equal to, or better than, the product specified.
- 10.3 Bids for alternate items shall be stated in the appropriate brand on the proposal form, or if the proposal form does not contain blanks for alternates, bidder MUST attach to the specification documents on Company letterhead a statement identifying the manufacturer and brand name of each proposed alternate, plus a complete description of the alternate items including illustrations, performance test data and any other information necessary for an evaluation. The bidder must indicate any variances by item number from the specification document no matter how slight. Bidder must fully explain the variances from the specification document, since brochure information may not be sufficient.
- 10.4 If variations are not stated in the proposal, it will be assumed that the item being bid fully complies with the County's specifications.

#### **11. DEMONSTRATIONS/SAMPLES**

- 11.1 Bidders shall demonstrate the exact item(s) proposed within seven (7) calendar days from receipt of such request from the County.
- 11.2 Such demonstration can be at the County delivery location or a surrounding community.
- 11.3 If bidder does not have an item in the area, it will be at the bidder's expense to send appropriate County personnel to the nearest location to view and inspect proposed item(s).
- 11.4 If items are small and malleable, and the bidder is proposing an alternate product, the bidder MUST supply a sample of the exact item. Samples will be returned at bidder's expense after receipt by the County of acceptable goods. Bidders must indicate how samples are to be returned.

#### **12. DELIVERY**

- 12.1 Each bidder shall state on his proposal form the date upon which he can make delivery of all equipment or merchandise. Time required for delivery is hereby made an essential element of the bid.
- 12.2 The County reserves the right to cancel orders, or any part thereof, without obligation, if delivery is not made within the time(s) specified on the proposal form.
- 12.3 All bids shall be based upon inside delivery of the equipment or merchandise F.O.B. the County at the location specified by the County, with all transportation charges paid.

#### **13. WARRANTIES, GUARANTEES AND MAINTENANCE**

- 13.1 Copies of the following documents must accompany the bid proposal for all items being bid:
  - 13.1.1 Manufacturer's warranties and/or guarantees.
  - 13.1.2 Bidder's maintenance policies and associated costs.
- 13.2 As a minimum requirement of the County, the bidder will guarantee in writing that any defective components discovered within a one (1) year period after the date of acceptance shall be replaced at no expense to the County. Replacement parts of defective components shall be shipped at no cost to the County. Shipping costs for defective parts required to be returned to the bidder shall be paid by the bidder.
- 13.3 Bidder Warrants and represents to the County that all software/firmware/ hardware/equipment /systems developed, distributed, installed or programmed by Bidder pursuant to this Specification and Agreement.
  - 13.3.1 That all date recognition and processing by the software/firmware/hardware/equipment/system will include the four-digit-year format and will correctly recognize and process the date of February 29, and any related data, during Leap years; and
  - 13.3.2 That all date sorting by the software /firmware/hardware/ equipment/system that includes a "year category" shall be done based on the four-digit-year format. Upon being notified in writing by the County of the failure of any software/ firmware/ hardware /equipment /systems to comply with this Specification and Agreement, Contractor will, within 60 days and at no cost to the County, replace or correct the non-complying software/ firmware/ hardware/ equipment/ systems with software/firmware/ hardware/equipment/systems that does comply with this Specification and Agreement.
  - 13.3.3 No Disclaimers: The warranties and representations set forth in this section 13.3 shall not be subject to any disclaimer or exclusion of warranties or to any limitations of Licensor's liability under this Specification and Agreement.

#### **14. ACCEPTANCE OF MATERIAL**

- 14.1 All components used in the manufacture or construction of materials, supplies and equipment, and all finished materials, shall be new, the latest make/model, of the best quality, and the highest grade workmanship.
- 14.2 Material delivered under this proposal shall remain the property of the bidder until:
  - 14.2.1 A physical inspection and actual usage of this material is made and found to be acceptable to the County; and
  - 14.2.2 Material is determined to be in full compliance with the specifications and accepted proposal.
- 14.3 In the event the delivered material is found to be defective or does not conform to the specification documents and accepted proposal, then the County reserves the right to cancel the order upon written notice to the bidder and return materials to the bidder at bidder's expense.
- 14.4 Successful bidder shall be required to furnish title to the material, free and clear of all liens and encumbrances, issued in the name of the Lancaster County, Nebraska, as required by the specification documents or purchase orders.
- 14.5 Selling dealer's advertising decals, stickers or other signs shall not be affixed to equipment. Vehicle mud flaps shall be installed blank side out with no advertisements. Manufacturer's standard production forgings, stampings, nameplates and logos are acceptable.

#### **15. BID EVALUATION AND AWARD**

- 15.1 The signed bid proposal shall be considered an offer on the part of the bidder. Such offer shall be deemed accepted upon issuance by the County of purchase orders, contract award notifications, or other contract documents appropriate to the work.
- 15.2 No bid shall be modified or withdrawn for a period of sixty (60) calendar days after the time and date established for receiving bids, and each bidder so agrees in submitting the bid.
- 15.3 In case of a discrepancy between the unit prices and their extensions, the unit prices shall govern.
- 15.4 The bid will be awarded to the lowest responsive, responsible bidder whose proposal will be most advantageous to the County, and as the County deems will best serve their requirements.
- 15.5 The County reserves the right to accept or reject any or all bids; to request rebids; to award bids item-by-item, by groups, or "lump sum"; to waive irregularities and technicalities in bids; such as shall best serve the requirements and interests of the County.

#### **16. INDEMNIFICATION**

- 16.1 The bidder shall indemnify and hold harmless the County, its members, its officers and employees from and against all claims, damages, losses, and expenses, including, but not limited to attorney's fees arising out of or resulting from the performance of the contract, provided that any such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property other than goods, materials and equipment furnished under this contract) including the loss or use resulting therefrom; is caused in whole or part by any negligent act or omission of the bidder, any subcontractor, or anyone directly or indirectly employed by any one of them or anyone for whose acts made by any of them may be liable, regardless of whether or not it is caused by a party indemnified hereunder.
- 16.2 In any and all claims against the County or any of its members, officers or employees by an employee of the bidder, any subcontractor, anyone directly or indirectly employed by any of them or by anyone for whose acts made by any of them may be liable, the indemnification obligation under paragraph 16.1 shall not be limited in any way by any limitation of the amount or type of damages, compensation or benefits payable by or for the bidder or any subcontractor under worker's or workmen's compensation acts, disability benefit acts or other employee benefit acts.

#### **17. TERMS OF PAYMENT**

- 17.1 Unless other specification provisions state otherwise, payment in full will be made by the County within thirty (30) calendar days after all labor has been performed and all equipment or other merchandise has been delivered, and all such labor and equipment and other materials have met all contract specifications.

#### **18. LAWS**

- 18.1 The Laws of the State of Nebraska shall govern the rights, obligations, and remedies of the Parties under this proposal and any agreement reached as a result of this process.

#### **19. AFFIRMATIVE ACTION**

- 19.1 The City of Lincoln-Lancaster County Purchasing Division provides equal opportunity for all bidders and encourages minority businesses and women's business enterprises to participate in our bidding process.

# **SPECIFICATIONS**

## **REMOVAL AND INSTALLATION OF NEW ROOF**

### **GENERAL INSTRUCTIONS TO BIDDERS**

**1. Start Date**

Work must begin no later than three(3) weeks after award of the contract, or as soon as weather conditions permit, unless otherwise specified.

**2. Completion Date**

All specified work shall be completed by October 15, 2004.

**3. Questions**

Questions regarding this bid can be directed to Don Killeen, Lancaster County 402-441-7356. If the Contractor feels a conflict exists between what is considered good roofing practices and these specifications, he shall state in writing all objections prior to submitting quotations. It is the Contractor's responsibility during the course of the work to bring to the attention of the Owner's representative any defective membrane, insulation or deck discovered, where not previously identified.

**4. Responsibility of Measurements and Quantities**

The bidding Contractor's shall be solely responsible for the accuracy of all measurements and for estimating the material quantities required to satisfy these specifications.

**5. Pre-job Meeting**

The pre-job meeting shall be held prior to the start of the project. This meeting shall include the Roof Manufacturer's Representative, the Contractor and project foreman, and the Owner's representative. The condition of the buildings and grounds area shall be recorded, and the Contractor shall be responsible for the correction and/or repair of an additional damage to the facilities resulting from the related work, and in addition to the conditions noted at the pre-job meeting.

**6. Discrepancies and Addendum**

Should a bidder find any discrepancies in the specifications, or should they be in doubt as to their meaning, they shall notify City/County Purchasing at once, who will send a written addendum to all bidders concerned. Oral instructions or decisions, unless confirmed by addendum, will not be considered valid or binding. All discrepancies must be submitted no later than five (5) days prior to the due date. No extras will be authorized because of failure of the Contractor to include work called for in the addendum in his bid.

City/County Purchasing Division  
"K" Street Complex (SW Wing)  
440 So. 8<sup>th</sup> Street, Suite 200  
Lincoln, NE 68508  
Phone: 402-441-8309  
Fax: 402-441-6513  
Email: ksmith@lincoln.ne.gov

## **7. Competency of Bidder**

- 7.1 To enable the Owner to evaluate the competency and financial responsibility of the Contractor, the low bidder shall, when requested by Owner, furnish the following information, which shall be sworn to under oath by him or by a properly authorized representative of the bidder.
  - 7.1.1 The address and description of the bidder's plant and place of business.
  - 7.1.2 The name and/or articles of co-partnership or incorporation.
  - 7.1.3 Itemized list of equipment available for use on the project.
  - 7.1.4 Contractor will furnish statement upon request of the Owner. Statement is to be valid and current. The Owner may require that any of the items contained be further verified.
  - 7.1.5 Such additional information as may be required that will satisfy the Owner that the bidder is adequately prepared in technical experience, or otherwise, to fulfill the contract.

## **8. REFERENCE CHECKS AND PAST EXPERIENCE**

The following will be considered in the award of this project:

- 8.1 Expertise as shown by past work, and judged from the standpoint of workmanship and performance history.
- 8.2 Uncompleted work under other contracts, which, in the judgment of the Owner, might hinder or prevent the prompt completion of additional work if awarded.
- 8.3 Being in arrears on existing contracts, litigation with an Owner, or having defaulted on a previous contract.

## **9. Sub-Contractors**

The contractor shall submit in writing the names and places of business of all sub-contractors. The standing and ability of the Contractor and subcontractors will be taken into consideration and agreed upon before awarding the contract.

## **10. Membrane Submittals**

- 10.1 The Bidder must submit the following to Don Killeen, County Property Manager office up to three days prior to bid opening. Bidders will be notified of approvals no later than three days before the bid opening.

Lancaster County Property Management  
Attn: Don Killeen, Property Manager  
920 "O" Street, Suite 203  
Lincoln, NE 68508  
Phone: 402-441-7356  
Fax: 402-441-8101

- 10.1.1 Submit certification that the roof system furnished is approved by Factory Mutual, Underwriters Laboratories, or Warnock Hersey for external fire E-108 Class 1A and that the roof system is adhered properly to meet or exceed 1-60 wind uplift.

- 10.1.2 Specification Data Sheets to include manufacturer's technical product data, installation instructions, and recommendations for each type of roofing product required. Include data substantiating that materials comply with specified requirements.
- 10.1.3 For all modified bituminous sheet roofing include independent test data according to ASTM designation D-5147-91 " Standard Test Methods for Sampling and Testing Modified minus Sheet Material" substantiating that materials comply with specified requirements. Submit this verification as part of the Manufacturer's Qualifications Statement.
- 10.1.4 List of three jobs where the proposed material has been used in a similar roofing system as that which is specified and within a one hundred mile radius from the location of the specified job. In addition, the three jobs must be at least three years old and be available for the Owner, or Owner's Representative to inspect. Submit this verification as part of the Manufacturer's Qualifications Statement.
- 10.1.5 Submit signed affidavit from manufacturer attesting to the validation of the Manufacturers Qualification Statement.
- 10.1.6 Submit signed and completed Bidders Qualification Statement as outlined in Qualifications of Bidders.
- 10.1.7 Un-executed Manufacturer's warranty.
- 10.1.8 Certified copy of Roofing Manufacturer's ISO 9001 compliance Submit this verification as part of the Manufacturer's Qualifications Statement.
- 10.2 Provide with your bid a twelve by twelve inch samples of all roll goods.
- 10.3 Provide current certificate from an accredited testing laboratory comparing the physical and performance attributes of the proposed material with those of the specified materials using ASTM D 5147 test methods. Testing will be done at 77degrees F.
- 10.4 Product data for each product to be used on the project. Including data substantiating that materials comply with requirements.
- 11. **Approved** - Wherever materials are specified to be "approved" or an approved pattern, make or design, it is understood that before installation of such materials the written approval of the Owner for same must be obtained especially for this work.
- 12. **Approved Substitute** - Whenever it is permitted in these specifications to substitute for a designated brand or grade of materials or workmanship, it is understood that in such case the written approval of the Owner for such substitution must be obtained especially for this work.
- 13. **Manufacturers** - To demonstrate the qualifications of the roofing system manufacturer for the project, each bidder must submit prior to 3 days before the Bid Due Date, the Statement of Roofing Manufacturers Qualifications.
  - 13.1 This statement is to verify the following information: roofing system manufacturer shall have minimum of 12 years experience in manufacturing modified bitumen roofing products in the United States and be ISO 9002 certified.
  - 13.2 The material manufacturer supplying material for the building owner's roofs must manufacture at least 70% of the materials they supply, in facilities actually owned or solely leased by said manufacturer.
  - 13.3 The material manufacturer shall submit verification of the Statement by affidavit of corporate officer. Subject to compliance with requirements, including submittal of acceptable form of warranty with bid, provide products by one of the following:

- 13.3.1 The Garland Company (our quality standard)
- 13.3.2 Owner Approved alternates

#### **14. Guarantees**

- 14.1 Manufacturer's Warranty - Submit executed copy of roofing manufacturer's standard Service Warranty agreement including flashing endorsement, signed by an authorized representative of modified bitumen sheet roofing system manufacturer, on form approved by Owner prior to award of contract.
  - 14.1.1 Warranty period to be 30 years from date of substantial completion.
  - 14.1.2 Owner's representative must be present when manufacturer's representative visits the site to approve application for warranty.
- 14.2 Additional Warranty - In addition to this warranty, the roofing Contractor shall also provide Midwest Roofing Contractor's Association a two year guarantee on all products and installation, including insulation, metal flashing and items not covered by manufacturer's warranty.

Warranties and guarantees must be provided to Owner before application for final payment.

#### **15. Asbestos Presence**

- 15.1 If the presence of asbestos exists, the contractor shall provide the labor necessary to properly remove and dispose of the asbestos according to OSHA Regulations and provide proper documentation to the Owner's Representative.

## **GENERAL CONDITIONS**

### **1. DESCRIPTION**

The work consists of complete removal of the existing roof system down to the decking, furnishing and installing all roofing, insulation, and sheet metal, as illustrated on the accompanying drawings and as specified herein.

### **2. LOCAL RULES**

The Owner has certain rules and the Contractor and his personnel shall abide by them. The Contractor shall contact the Owner's representative for specific information regarding the rules governing all operations of this project.

### **3. CONCURRENT OPERATIONS**

Because other activities of the Owner will be preceding at the same time as the work covered by this specification, the Contractor shall cooperate with the Owner's representative to insure that all contract work progresses in a manner, which does not conflict with other activities.

### **4. CLEAN UP**

Contractor shall be responsible for maintaining all work areas in a neat and orderly manner on a daily basis. Immediately upon completion, all clean up shall be performed to the satisfaction of the Owner's representative.

**5. MAINTENANCE OF BUILDINGS AND GROUNDS**

Interior of building below specified are and grounds shall be inspected prior to construction and returned to original condition upon completion to the satisfaction of the Owners' representative.

**6. SAFETY**

The Contractor shall comply with all applicable provisions of the Occupational Safety and Health Act throughout the duration of the specified work.

**7. INSPECTION OF WORK IN PROGRESS AND UPON COMPLETION**

7.1 When directed by the Owner's representative, the Contractor shall cut not more than four (4) cores of approximately 200 square inches each from every newly constructed built-up roof area to establish the quality of the built-up roof system, and shall restore all such areas to sound and watertight conditions. Contractor will be responsible for any discrepancies in quality of work and misrepresentation of materials by contractor or the manufacturer.

7.2 When such core cuts disclose any deficiency in materials or unsoundness of construction, the Contractor shall, at his own expense, correct the deficiencies to the satisfaction of the Owner's representative.

7.3 At the completion of all patching flashing repair and cleaning, and prior to any resurfacing and restoration work, the Contractor shall notify the Owner's representative. Twenty-four (24) hours notice shall be given to above, at which time an inspection of the prepared roof will be made.

8. The Owner shall authorize the material manufacturer's representative to examine the work in progress, as well as upon completion. In order to assist in ascertaining the extent to which the materials and procedures conform to the requirements of these specifications and to the published instruction of the material manufacturer.

9. The authorized material manufacturer's field representative shall be responsible for:

9.1 Rendering inspections a minimum of 3 times per week, the manufacturer's representative shall provide written reports documenting progress and photos to be filed weekly with Mr. Don Killeen, Lancaster County. Inspector will be a full time employee of the roofing manufacturer.

9.2 Keeping the Owner's representative informed after daily inspections as to any changes in the progress and quality of the work as observed.

9.3 Immediately calling to the attention of the Owner's representative and the Contractor those matters observed which he considers to be in violation of the contract requirements.

9.4 Reporting to the Owner's representative in writing any failure or refusal of the Contractor to correct unacceptable practices called to his attention.

9.5 Supervise the taking of test cuts and the restoration of such areas. Test cuts may be taken to verify all materials and installation conform to specifications.

9.6 Confirming, after completion of the work based on his observations and tests, that he has observed no application procedures in conflict with the specifications other than those that may have been previously reported. Final payment will not be released until his confirmation has been received by the Owner.

10. The presence and activities of the material manufacturer's field representative shall in no way relieve the Contractor of his contractual responsibilities. In the event of a dispute the Owner's representative shall have final authority.

# DETAILED SPECIFICATIONS

## 1. SCOPE OF WORK

- 1.1 All work specified herein and on drawings shall be performed by an approved Roofing Contractor having competent, experienced mechanics capable of producing the required work.
- 1.2 The Roofing Contractor shall perform all work as specified and required to roof areas as designated.
- 1.3 Necessary Mechanical disconnects and reconnects shall be provided by the Roofing Contractor and executed by an approved Mechanical/Electrical Contractor.
- 1.5 All necessary plumbing shall be included in bid price.
- 1.6 The following general work is included;
  - 1.6.1 Remove existing roof membranes, flashings, etc., down to the existing Expanded Polystyrene Insulation. (EPS) and dispose of properly. Remove any unused curbs as designated by the Owner's Representative.
  - 1.6.2 Replace any wet insulation- Equal in value
  - 1.6.3 Install new curb for ventilation fan
  - 1.6.4 Repair all damaged decking as necessary.
  - 16.5 Mechanically attach ½" Wood Fiber Insulation.
  - 16.6 Drains shall be tapered and sumped a minimum of 4'X 4'.
  - 16.7 Install Garland High Performance Modified Built-Up-Roof System per Specifications.
  - 16.8 Install Garland HPR Modified Flashing System as specified.
  - 16.9 Raise units as necessary and install new mechanical unit drip edge counter flashing with new 24 gauge surface mount counter-flashing as detailed.
  - 16.10 Install new Pre-Manufactured 24 gauge raised metal edge and fascia at roof perimeter.
  - 16.11 Replace any broken drain strainers with new cast iron drain strainers drains.
  - 16.12 Coat all flashings with Garla-Brite Reflective coating.



# MATERIALS

## HIGH PERFORMANCE MODIFIED BUILT-UP-ROOF SYSTEM

### 1. PRODUCTS

The Owner reserves the right to select and utilize products that will perform the best with the related construction materials and will afford the maximum protection for the facility.

1.1 No products shall be used that contain asbestos.

1.2 Products used should meet the following performance requirements.

### 2. BITUMINOUS MATERIALS

2.1 Asphalt Primer: ASTM D41

Viscosity	Zahn Cup	18-21
Non-Volatile Cont. Fed. Test 141	44%	
Density	GRC 930	7.75
Flash Point	ASTM D 93	100°F. min

2.2 Asphalt Roofing Mastic: ASTM D-2822, Type II.

2.3 Heated Asphalt: ASTM D-312, Type III and Type II

2.4 Elastomer Cement: Thermoplastic modified bituminous-based mastic with 500% elongation at 0°F.

Consistency	ASTM D2196-8132	
Density	ASTM D1475-608.1/g	
Flash point	ASTM D93-80	80°F.
Non-Volatiles	STM D4479	60% min.
Perm Rating	ASTM E-96	.03
Resistance to sag	GRC 911 77°F. 1/4"	None
Tensile Strength	ASTM D412-83	100 psi
Elongation	ASTM D412-83	650%
Elongation after accelerated aging	GRC 912	500%

### 3. SHEET MATERIALS

3.1. Garland Versiply 40 base flashing ply: ASTM 5147

3.2. HPR Type IV felt: ASTM D-2178

3.3 FIELD AND FLASHING MEMBRANE- ASTM D6162  
SIS/SEBS/SE Modified Bitumen Mineral Surfaced Field and Flashing Membrane.

3.3.1 Modified Membrane: STRESSPLY "E" FR; 80 mil SIS, ES and SBS (Styrene-Isoprene-Styrene, Ethylene Styrene and Styrene-Butadiene-Styrene) rubber modified roofing membrane with fire retardant characteristics and reinforced with a dual fiberglass scrim and polyester mat.

3.3.2	Elongation of modified asphalt compound - 1500%	
3.3.3.	Tensile Strength & Elongation (ASTM D-2523, D-5147)	
	MD (@ 2"/min. pull rate)Tensile/lb.	450
	Elongation	6.0%
	CMD (@ 2"/min. pull rate)Tensile /lb.	500
	Elongation/%	6.0%
	Tear Resistance (ASTM D-4073)	
	MD/lbs.	900
	CMD/lbs.	900
	Low Temp. Flex.	-30°

#### 4. ROOF INSULATION

##### 4.1 HIGH DENSITY FIBERBOARD ROOF INSULATION

- 4.1.1 Qualities: Rigid, composed of interlocking fibers factory blended treated with asphalt on the top side.
- Board Size: 4'x4'.  
Thickness: Minimum 1/2"
- 4.1.2 Source: Celotex Temple Inland, GAF Building Materials Corporation or Approved Equivalent  
Insulation board shall meet the following requirements:  
UL , WH, FM listed under Roofing Systems  
Federal Specification LLL-I-535-B
- Physical Properties:
- |                                   |                |                    |
|-----------------------------------|----------------|--------------------|
| Dry Density                       | ASTM C-208     | 17.5 pcf           |
| Compressive Strength              | ASTM C-165     | 45 psi min.        |
| Linear Expansion                  | ASTM C-208,209 | 0.5% max.          |
| Foam Core Density                 | ASTM C-1622    | 2.0 pcf min.       |
| Water Absorption                  | ASTM C-208     | 10% max.           |
| R-Factor HR per inch<br>Thickness | ASTM C-518     | 2.5 (Design Value) |
- 4.1.3 Fiber Cant and Tapered Edge Strips: Performed rigid insulation units of sizes/shapes indicated, matching insulation board or of perlite or organic fiberboard, as per the approved manufacturer.
- 4.1.3.1 Acceptable Manufacturers
- a. The Garland Company
  - b. Celotex
  - c. Schuller Roofing Systems
  - d. International Permalite, Inc.
  - e. Approved Equivalent

## **5. RELATED MATERIALS**

- 5.1 Miscellaneous Fasteners:
  - 5.1.1 TEK #1 or #4 screws
  - 5.1.2 Expanding lead fasteners 1/4" min.
  - 5.1.3 Self-compressing drywall fasteners.
- 5.2 Caulking: Single component terpolymer meeting FS TT-S-00230C.  
Coatings: ASTM D 2284 Type 1 for all flashings.  
Sealants: Silicone based for parapet walls.
- 5.3 Lead: 4# sheet lead. ASTM B 29-79 (1984)
- 5.4 Metal Counter-Flashing: 24 gauge surface mounted counter-flashing.
- 5.5 Raised Metal Edge Fascia. Pre-Manufactured by roof system manufacturer.
- 5.6 Drains: New Cast iron installed to manufactures guidelines.

# **EXECUTION**

## **MODIFIED BUILT-UP-ROOF INSTALLATION**

### **1. PREPARATION**

- 1.1 Do not remove more existing membrane or flashings than can be restored completely watertight in one day.
- 1.2 Remove all existing membranes, flashings, aggregate and debris down to dry existing EPS Insulation. Properly dispose of all debris.
- 1.3 Remove and dispose of all metal flashings.
- 1.4 Thoroughly inspect the roof deck and EPS Insulation where applicable and report any deterioration found to the Owner's Representative and the Garland Representative.
- 1.5 If any decking or insulation requires repair or replacement, Owner must give written approval to proceed with repair or replacement and such work shall be charged on a unit price basis.
- 1.6 All wood mechanical/electrical blocks are to be replaced as part of this project with new treated wood or redwood.
- 1.7 Any pipes, curbs, conduits or equipment that the Owner determines to be no longer needed shall be removed under this contract.
- 1.8 All curbs, soil stacks, and other flashing surfaces shall be extended to a minimum of 7-8" above the horizontal roof surface.

1.9 Provide chute and/or tarp for removal of all debris from the roof and pick up all debris on the ground daily. Keep work area on the ground well policed.

1.10 Provide truck or dumpster for daily removal of all roofing related debris.

## **2. INSULATION:**

2.1 Over properly prepared EPS Insulation , Mechanically attach ½” Wood Fiber to the metal deck using an approved fastener. Attachment should meet or exceed FM 1-90.

2.2 Be sure to stagger joints so new insulation joints are not directly in line with existing EPS. Stagger end joints of boards so all open joints will be eliminated.

2.2.1 Each insulation board shall be butt firmly against adjoining panels.

2.2.2 All open joints shall be eliminated.

2.3 Approved insulation shall be tapered around roof drains and scuppers.

2.3.1 Tapered insulation sump shall start with a thickness of one-half at drain bowl to the specified dimension of three feet from the center line of the drain.

2.3.2 Install tapered insulation sump in such a way to provide proper slope for runoff.

2.3.3 Shape insulation with tool as required so completed surface is smooth and flush with ring of drain.

2.3.4 Under no circumstances will the membrane be left unsupported in an area greater than ¼”.

2.3.5 Install recovery board over tapered insulation sump as required.

2.4 All boards shall be cut and fitted where the roof deck intersects a vertical surface. The boards shall be cut to fit a minimum of ¼” away from the vertical surface.

2.5 Install no more insulation at one time than can be roofed on the same day.

2.6 Install temporary water cut-offs at completion of each day’s work and remove upon resumption of work.

2.7 Cant Strips/Tapered Edge Strips: Install preformed 45-degree cant strips at junctures of vertical surfaces. Provide preformed, tapered edge strips at perimeter of edges of roof that do not terminate at vertical surfaces and/or indicated on the drawings. Tape joints of insulation as per manufacturer’s requirements.

2.8 New wood nailers of thickness equal to height of insulation shall be installed at all perimeters to receive raised metal edge.

## **3. GLASS FELT INSTALLATION**

3.1 Starting at the low point of the roof install three plies of Type IV fiberglass felts shingle fashion overlapping each ply 12". Place ply sheets to ensure water will flow perpendicular to the direction of the felt.

3.2 Embed each ply in a uniform and continuous mopping of Type III steep asphalt applied at a rate of 30 lbs. per 100 sq. ft.

3.3 Lap ply ends 6" and stagger end laps 12".

- 3.4 No voids, wrinkles, or fishmouths will be allowed.
- 3.5 There must be a minimum of one (1) inch of hot asphalt evident at all seams.
- 3.6 Extend base plies a minimum of 2" above all cant strips.
- 3.7 Cant strips shall be a minimum of 3"x3" and shall be installed at the intersection of all horizontal and vertical flashing surfaces securely adhered in place.

#### **4. MODIFIED MEMBRANE APPLICATION**

- 4.1 The Modified Membrane shall be solidly bonded to the base layers with Type III steep asphalt applied at a rate of 30 Lbs. per 100 sq. ft. The roll must push a puddle of asphalt in front and asphalt must be visible on both sides.
- 4.2 Subsequent rolls of modified membrane shall be installed across the roof as above with a minimum 4" side lap and 8" end lap. End laps shall be staggered a minimum of 12".
- 4.3 The modified membrane shall be laid in the same direction as the base plies, however, the laps shall not coincide with those of the base plies.
- 4.4 Apply asphalt no more than 10' ahead of the roll being embedded.
- 4.5 Extend the membrane to a point a minimum of 4" above all cant strips in a full bedding of hot asphalt.
- 4.6 Care shall be taken not to stretch or buckle the Membrane during application.
- 4.7 No voids, wrinkles, or fishmouths will be allowed.
- 4.8 There must be a minimum of two (2) inches of hot asphalt evident at all seams.

#### **5. GENERAL FLASHING REQUIREMENTS**

- 5.1 Prepare all walls and penetrations to be flashed with asphalt primer applied at a rate of 200 sq. ft. per gal.
- 5.2 Apply one layer of Versiply 40 to the wall area well up underneath the counter-flashings embedded in Type III steep asphalt applied at a nominal rate of 30 lbs. per 100 sq. ft.
- 5.3 Install Modified Flashing Membrane beginning at a point at least 6" out onto the roof beyond the edge of the cant strip and extending up the wall to a point at least 4" under the lip of the counter-flashing or to a fixation point at least 4" above the horizontal plane of the roof.
- 5.4 All laps between flashing plies shall be a minimum of 4".
- 5.5 Using specified fasteners, fasten new termination bar at 9" O.C. to the nailer curb.
- 5.6 Apply a three-course of mastic and reinforcement at the top of the flashing plies prior to attaching the counter-flashing.
- 5.7 All seams at the vertical flashings shall receive a three course of mastic and webbing.

- 5.8 Install a 1-piece mounted surface mount type counter-flashing per detail drawing. Apply Garla-Flex modified asphalt and mesh to backside of mounting face and fasten every 9" O.C. with screws or expanding lead fasteners.
- 5.9 Fill caulking groove with Garland Terpolymer Caulk applied in two separate applications creating a full watershed joint.
- 5.10 Install new metal end caps where necessary.
- 5.11 All flashing heights shall be a minimum of 8" above the plane of the finished roofing system.
- 5.12 Coat all flashings with Garla-Brite reflective coating

## **6. FLASHINGS AT PIPES, PROJECTIONS, PITCH PANS AND CONDUITS**

- 6.1 All SOIL STACKS shall receive new 4 Lb. lead flashings.
  - 6.1.1 The lead shall be large enough to leave a continuous 6" flange on the roof surface and shall extend up the pipe far enough to allow 1" to be crimped down into the pipe interior.
  - 6.1.2 If diameter of pipe is 2" or less, cut off lead at top of pipe and install lead collar.
  - 6.1.3 Base flange shall be set in elastomer cement covering the entire bottom of the flange.
  - 6.1.4 Flashing membrane shall be installed as a "target" ply over the flange area and extending out onto the roof membrane a minimum of 8" from the flange perimeter.
  - 6.1.5 A bead of elastomer shall be installed at the base of the vertical portion of the pipe against the membrane.
- 6.2 All PITCH PANS shall be installed or replaced with new 24 gauge galvanized sheet metal pans:
  - 6.2.1 New pan shall be constructed so that a continuous 4" flange is in place around the perimeter, sides shall be a minimum of 3" high and hemmed to the outside.
  - 6.2.2 There shall be a minimum of 2" clearance between the sides of the pan and the projection that it is flashing.
  - 6.2.3 Pan shall be cleaned of oil residue and primed with asphalt primer.
  - 6.2.4 Entire bottom of pan flange shall be coated with roof elastomer and shall be securely seated in place.
  - 6.2.5 Install flashing membrane over the flange and extending onto the roof a minimum of 8" on all sides.
  - 6.2.6 Fill pitch pan half full with non-shrink grout and fill full with roof elastomer tapered in a watershed fashion away from the projection.
- 6.3 Install all CONDUIT and mechanical lines and pipes resting on redwood or treated wood weight displacement supports.

- 6.3.1 Install an additional ply of flashing membrane at least 4" wider than the wood block on all sides onto the roof membrane fully adhered.
- 6.3.2 Set wood support onto this pad in roof elastomer covering the bottom of the block completely.
- 6.3.3 Anchor conduit or pipe to the wood block with screws and brackets of similar metal to that of pipe.
- 6.3.4 Wood blocks should be of sufficient size and spacing to adequately support conduit or pipe off roof membrane without bowing. As a minimum a block shall occur every 10' O.C.
- 6.3.5 Large gas lines and other heavy pipes shall utilize floating roller supports as installed by mechanical tradesmen.
- 6.4 Install metal STACK flanges in same manner as described for SOIL STACKS.
- 6.5 Install all METAL BASE FLANGE curbs in the following manner:
  - 6.5.1 Base flange shall be a minimum of 4" in width and side walls shall be even and watertight.
  - 6.5.2 Apply roof elastomer to entire underside of flange before seating on roof and anchor securely.
  - 6.5.3 Primer flange area and install flashing membrane beginning at base of vertical wall and extending out onto the roof membrane a minimum of 8". Seal area at angle vertex with roof elastomer. Coat all flashings with Garla-Brite reflective coating.

## **7. SURFACING APPLICATION**

- 7.1 Mineral Surfaced Membrane System: While bleed out from the side and end laps are still hot, hand broadcast minerals into asphalt bleed out for a monolithic appearance. Aluminize any areas of improper adherence of minerals and rebroadcast minerals while coating is still wet.

## **8. DAILY AND TEMPORARY WATER-STOP TIE-INS**

- 8.1 Remove embedded gravel/debris from top ply of felt along termination. Width: 18 Inches.
- 8.2 Adhere twelve (12) and eighteen (18) inch wide ply sheets from exposed deck to existing roofing with a continuous 1/16" thick application of tie-off mastic. Glaze cut-off with surfacing mastic. Extend eighteen (18) inch wide felt three (3) inches either side twelve (12) inch felt.
- 8.3 Install "Dead-man" insulation filler at insulation staggers.
- 8.4 Extend roofing system at least twelve (12) inches onto prepared area of adjacent roofing. Seal edge with six (6) inch wide reinforcing membrane embedded between alternate courses of tie-off mastic.
- 8.5 At beginning of next day's work, remove temporary connection by cutting felts evenly along the edge of the existing roof system. Remove "Deadman" insulation fillers.

**9. METAL PERIMETER FLASHINGS**

9.1 New Metal fascia shall be 24 gauge Pre-Manufactured from the roofing system manufacturer.

**10. OTHER MATTERS**

10.1 All sheet metal work will be done by a qualified sheet metal contractor.

10.2 Contractor shall provide necessary precautions to minimize odors entering the facility.

10.3 All details and practices not specifically covered by these specifications and drawings shall conform to the current NRCA Manual.

10.4 Contractor is to provide his own toilet facilities on the job site. Building access will be limited.

10.5 No more roofing will be removed in any single day than can be roofed through the top layer of membrane that day. Water can not be tolerated into the building at any time during the re-roofing project.

10.6 Contractor will supply his own access to the roof from the outside of the building in an area to be designated by the Owner. Access to the building will be removed each evening or at the end of each work day to prevent unauthorized personnel from gaining access to the roof.

10.7 Contractor will keep all work and storage areas clean and neat on a daily basis. All work area must be contained by use of snow fencing or other suitable restraints to prevent access from unauthorized personnel.

10.8 All materials stored on the job site that are vulnerable to weather must be covered.

10.9 All perimeter and projection flashings shall be raised to a minimum height of 8" above horizontal plane of the finished roof membrane system.

10.10 No phase roofing.

10.11 Contractor shall note that a minimum of 4 (four) proper fire extinguishers must be on the roof at all times.

10.12 Contractor shall strictly follow City of Lincoln's Safety programs and Procedures at all times.

***SEE CONSTRUCTION DETAILS ON  
ATTACHED DRAWINGS***



**CONSTRUCTION**

**DETAILS**

BASE OF UNIT EXTENDS  
1/2" MINIMUM [13mm]  
BEYOND AND DOWN OVER  
TOP OF CURB

SEALING MATERIAL—MUST  
BE CONTINUOUS ON THE  
PERIMETER

FLASHING RECEIVER

WOOD NAILER  
NOMINAL 2" X 4"  
[51mm X 102mm]

8" MIN.  
[203mm]

1" MINIMUM [25mm]

COUNTERFLASHING

FASTENERS 8" O.C.  
[203mm]

UNIT MOUNTING CURB

HPR MODIFIED MEMBRANE

CANT STRIP

INSULATIONS  
STAGGER ALL JOINTS  
FASTEN ACCORDING TO SPECIFICATION

BASE FLASHING PLY 6" MIN.  
[152mm] ON FIELD


HPR MODIFIED MEMBRANE FLASHING PLY  
9" MIN. [228mm] ON FIELD

FELT PLIES


METAL DECK


ALL PLIES SET IN BITUMEN  
SEE SPECIFICATION FOR SURFACING

CURB DETAIL/AIR HANDLING STATION  
N.T.S.





ALL PLIES SET IN BITUMEN  
SEE SPECIFICATION FOR SURFACING






ALL PLIES SET IN BITUMEN  
SEE SPECIFICATION FOR SURFACING


EXHAUST FAN DETAIL  
N.T.S.



PLUMBING STACK  
N.T.S.



ALL PLIES SET IN BITUMEN  
SEE SPECIFICATION FOR SURFACING




PITCH POCKET W/UMBRELLA  
N.T.S.


# THE GARLAND COMPANY, INC.

## R MER EDGE SNAP-ON FASCIA

FASCIAM 101





NOTE: INSTALL SCUPPERS AND MITERS FIRST  
ALLOW 3/8" GAP BETWEEN 10' SECTIONS  
FOR THERMAL MOVEMENT.  
REMOVE STRIPPABLE FILM AFTER INSTALLATION



R MER EDGE SNAP-ON FASCIA

N.T.S.



TYPICAL SECTIONS - MINERAL FINISH  
N.E.S.



# **LANCASTER COUNTY GENERAL CONDITIONS**

For the purpose and intent of this project, the enclosed “General Conditions, City of Lincoln, Nebraska 10/29/92)”, wherever “Owner” or “City of Lincoln (City)” is referenced it shall mean “Lancaster County”. In further clarification, it is understood that the City of Lincoln is not involved with this project, but rather Lancaster County is adapting the “General Conditions” to govern the administration of this project.

GENERAL  
CONDITIONS

City of  
Lincoln,  
Nebraska

10/29/92

<b>GENERAL TERMS .....</b>	<b>1</b>
I.        DEFINITIONS .....	1
II.       CONSTRUCTION AND INTENT .....	2
III.      OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS .....	3
<b>PRECONDITIONS AND ASSURANCES .....</b>	<b>3</b>
IV.      GENERAL PRECONDITIONS AND ASSURANCES .....	3
V.       UNIT PRICES .....	4
VI.      STATED CONDITIONS .....	4
<b>CITY .....</b>	<b>4</b>
VII.     INFORMATION AND SERVICES REQUIRED OF THE CITY .....	4
VIII.    CITY'S RIGHT TO STOP THE WORK .....	4
IX.      CITY'S RIGHT TO CARRY OUT THE WORK .....	4
X.       STORAGE OF MATERIALS .....	5
XI.      ALTERATIONS AND SUBSTITUTIONS .....	5
XII.     DEFECTIVE MATERIALS .....	5
XIII.    CITY SUPPLIED MATERIALS .....	5
<b>CONTRACTOR .....</b>	<b>5</b>
XIV.     REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR .....	5
XV.      SUPERVISION AND CONSTRUCTION PROCEDURES .....	6
XVI.     LABOR AND MATERIALS .....	6
XVII.    WARRANTY .....	7
XVIII.   PERMITS, FEES AND NOTICES .....	7
XIX.     PRE-CONSTRUCTION AND PROGRESS CONFERENCES .....	7
XX.      ALLOWANCES .....	7
XXI.     SUPERINTENDENT .....	8
XXII.    CONTRACTOR'S CONSTRUCTION SCHEDULES .....	8
XXIII.   DOCUMENTS AND SAMPLES AT THE SITE .....	8
XXIV.    SHOP DRAWINGS, PRODUCT DATA AND SAMPLES .....	8
XXV.     USE OF SITE .....	9
XXVI.    CONTRACTOR'S USE OF UTILITIES .....	9
XXVII.   CUTTING AND PATCHING .....	9
XXVIII.  CLEANING UP .....	9
XXIX.    ACCESS TO WORK .....	9
XXX.     ROYALTIES AND PATENTS .....	9
XXXI.    INDEMNIFICATION .....	10
XXXII.   PROTECTION OF WORK AND PROPERTY .....	10
XXXIII.  TRAFFIC CONTROL .....	10
XXXIV.   FAIR EMPLOYMENT PRACTICES .....	10
XXXV.    FAIR LABOR STANDARDS .....	11
<b>ARCHITECT .....</b>	<b>11</b>
XXXVI.   ARCHITECTS ADMINISTRATION OF THE CONTRACT .....	11
<b>CLAIMS &amp; DISPUTES .....</b>	<b>12</b>
XXXVII.  CLAIMS AND DISPUTES .....	12
XXXVIII. RESOLUTION OF CLAIMS AND DISPUTES .....	12
<b>SUBCONTRACTORS .....</b>	<b>13</b>
XXXIX.   AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK .....	13
XL.      CONTINGENT ASSIGNMENT OF SUBCONTRACTS .....	14

<b>CHANGES IN THE WORK .....</b>	<b>14</b>
XLI. CHANGES .....	14
XLII. CONSTRUCTION CHANGE DIRECTIVES .....	14
<b>TIME .....</b>	<b>15</b>
XLIII. PROGRESS AND COMPLETION .....	15
XLIV. DELAYS AND EXTENSIONS OF TIME .....	15
XLV. LIQUIDATED DAMAGES .....	15
<b>PAYMENTS AND COMPLETION.....</b>	<b>15</b>
XLVI. CONTRACT SUM .....	15
XLVII. SCHEDULE OF VALUES .....	15
XLVIII. APPLICATIONS FOR PAYMENT.....	16
XLIX. CERTIFICATES FOR PAYMENT .....	16
L. DECISIONS TO WITHHOLD CERTIFICATION .....	16
LI. PROGRESS PAYMENTS .....	17
LII. FAILURE OF PAYMENT .....	17
LIII. SUBSTANTIAL COMPLETION .....	17
LIV. PARTIAL OCCUPANCY OR USE .....	18
LV. FINAL COMPLETION AND FINAL PAYMENT .....	18
<b>SAFETY .....</b>	<b>19</b>
LVI. SAFETY PRECAUTIONS AND PROGRAMS.....	19
LVII. SAFETY OF PERSONS AND PROPERTY .....	19
LVIII. EMERGENCIES .....	20
<b>FINANCIAL SECURITY .....</b>	<b>20</b>
LIX. CONTRACTOR'S LIABILITY INSURANCE .....	20
LX. PROPERTY INSURANCE .....	21
LXI. PERFORMANCE BOND AND PAYMENT BOND.....	21
<b>TESTING AND CORRECTING WORK .....</b>	<b>21</b>
LXII. TESTS AND INSPECTIONS .....	21
LXIII. UNCOVERING OF WORK .....	22
LXIV. CORRECTION OF WORK .....	22
LXV. ACCEPTANCE OF NON-CONFORMING WORK .....	23
<b>MISCELLANEOUS TERMS .....</b>	<b>23</b>
LXVI. GOVERNING LAW .....	23
LXVII. SUCCESSORS AND ASSIGNS .....	23
LXVIII. WRITTEN NOTICE .....	23
LXIX. RIGHTS AND REMEDIES .....	23
LXX. COMMENCEMENT OF STATUTORY LIMITATION PERIOD .....	23
LXXI. INDEPENDENT CONTRACTOR .....	24
<b>TERMINATION OR SUSPENSION.....</b>	<b>24</b>
LXXII. TERMINATION BY THE CONTRACTOR .....	24
LXXIII. TERMINATION BY THE CITY FOR CAUSE .....	24
LXXIV. SUSPENSION BY THE CITY FOR CONVENIENCE .....	25
LXXV. TERMINATION BY THE CITY FOR CONVENIENCE .....	25

GENERAL TERMS .....	1
PRECONDITIONS AND ASSURANCES .....	3
CITY .....	4
CONTRACTOR .....	5
ARCHITECT .....	11
CLAIMS & DISPUTES .....	12
SUBCONTRACTORS .....	13
CHANGES IN THE WORK .....	14
TIME .....	15
PAYMENTS AND COMPLETION .....	15
SAFETY .....	19
FINANCIAL SECURITY .....	20
TESTING AND CORRECTING WORK .....	21
MISCELLANEOUS TERMS .....	23
TERMINATION OR SUSPENSION .....	24

## **GENERAL TERMS**

### **I. DEFINITIONS**

- A. Addendum (Addenda) shall mean the formal written instructions the City issued to prospective Bidders prior to the closing date for receipt of bids. Such instructions change or clarify the original plans or specifications, i.e., additions, deletions, modifications, or explanations.
- B. Advertisement shall mean the announcement the City made as required by law, stating the time and place for receiving bids for the Work.
- C. Architect shall mean the designated architect or engineer the City employed or contracted to provide design and other professional services related to the project. Architect shall include the Architect or the Architect's authorized representative.
- D. Bid shall mean the properly signed and guaranteed written offer of the Bidder to perform the Work. Bid shall include Proposals or other formal written offers to perform the Work.
- E. Bidder shall mean any individual, entity, firm, partnership, or corporation formally submitting a proposal to perform the Work or to supply materials for the Work. Bidder shall include any of the same acting through an authorized agent or representative.
- F. Change Order shall mean a written instrument the Architect or Contract Administrator issues and the Mayor and the Contractor approve to state the City and Contractor's agreement for a change in the Work. All Change Orders shall specify the method of payment, if any. All Change Orders shall specify adjustments in the Contract Sum or Contract Time, if any.
- G. City shall mean the City of Lincoln, Nebraska, and shall include the City's authorized representative.
- H. Claim shall include a demand or assertion by the City or Contractor seeking an adjustment to or interpretation of Contract terms, payment, time or other matters related to the Contract. The party making the Claim shall substantiate any such Claim.
- I. Construction Change Directive shall mean a written instrument the Architect or Contract Administrator issues and the City approves for a change in the Work within the scope of the Contract. Such changes shall include additions, deletions or other revisions. Such directive shall state a proposed basis for adjustment, if any, in the Contract Sum or Contract Time, or both. Construction Change Directives shall not invalidate the Contract in any event.
- J. Contract Documents shall include the Contract, Conditions of the Contract (General, Supplementary and other conditions), Drawings, Specifications, addenda issued prior to execution of the Contract, other documents listed in the Contract and modifications or other agreements required to complete the work issued after execution of the Contract. Unless specifically excluded in the Contract, Contract Documents shall also include the bidding requirements, Advertisement, Instructions to Bidders, sample forms, Contractor's Bid and Addenda. See also: Subparagraphs XIV(D); and XXIV(A).
- K. Contract shall mean the entire and integrated agreement between the City and Contractor. The parties may amend or modify the Contract only by Modification.
- L. Contract Time shall mean the time the Contract Documents allow for Substantial Completion of the Work. Contract Time shall include any changes the City authorized by Modification.
- M. Contractor shall mean the person or entity identified as such in the Contract. Contractor includes the Contractor or the Contractor's authorized representative. The contractor is always considered as an independent Contractor.
- N. Day shall mean calendar day including Sundays and Holidays. (See Subparagraph II(G), Time)
- O. Drawings shall include any graphic or pictorial portions of the Contract Documents showing the design, location and dimensions of the Work, including: plans, elevations, sections, details, schedules and diagrams related to the Work.
- P. Liquidated Damages shall mean the amount prescribed in the Contract Documents that the Contractor is to pay to the City for each Day after the contract completion date until the Substantial Completion Date. Liquidated Damages are actual damages the Contractor owes the City. The Contractor agrees such damages are not a penalty.
- Q. May shall be permissive.
- R. Mayor shall mean the Mayor of the City of Lincoln, Nebraska.
- S. Modification shall include any (1) written amendment to the Contract that both the City and Contractor have signed, (2) Change Order, (3) Construction Change Directive or (4) authorized written order the Architect issued for a minor change in the Work.
- T. Month shall mean a calendar month.

- U. Product Data shall include illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information the Contractor furnishes to illustrate materials or equipment for the Work.
- V. Project Manual shall mean the document assembled for the Work that may include the bidding requirements, sample forms, Conditions of the Contract and Specifications.
- W. Project shall mean the total construction related to the Work provided by this Contract. The Project may include construction by the City or by separate contractors.
- X. Samples shall include physical examples that represent materials, equipment or workmanship and establish standards for the Work.
- Y. Shall shall be mandatory.
- Z. Shop Drawings shall include drawings, diagrams, schedules and other data the Contractor or any Subcontractor, Sub-subcontractor, manufacturer, supplier or distributor specially prepared to illustrate some portion of the Work.
- AA. Specifications shall mean any written requirement for materials, equipment, construction systems, standards or workmanship for the Work, including performance of related services.
- BB. Sub-subcontractor shall mean a person or entity a Subcontractor hires or contracts to perform a portion of the Work at the site. Sub-subcontractor includes any Sub-subcontractor or an authorized representative of the Sub-subcontractor.
- CC. Subcontractor shall mean a person or entity the Contractor hires or contracts to perform a portion of the Work at the site. Subcontractor includes any Subcontractor or an authorized representative of the Subcontractor. Subcontractor shall not include any separate contractor the City hires or contracts or any subcontractors of such separate contractor.
- DD. Substantial Completion Date shall mean the date the City certifies as such in accordance with Paragraph LIII, Substantial Completion.
- EE. Substantial Completion shall mean the stage when the City determines (according to the Contract Documents) that the Work or a designated portion thereof is sufficiently complete, and when the Contractor has secured all required occupancy permits, if any, so the City can occupy or use the Work for its intended use.

- FF. Work Commencement Date shall mean the date established as such in the Contract. The Contractor shall not postpone such date by failure to act or by permitting or allowing persons or entities under the Contractor's responsibility to postpone such date.
- GG. Work shall include the construction and services the Contract Documents require, whether completed or partially completed, and all other labor, materials, equipment and services necessary to fulfill the Contractor's obligations. Work may constitute the whole or a part of the Project.

---

## II. CONSTRUCTION AND INTENT

- A. The General Conditions may refer to conditions that are not applicable to the Work. Such Conditions shall have no meaning.
- B. Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings shall not control the Contractor in dividing the work among Subcontractors or in establishing the extent of Work to be performed by any trade.
- C. Words and phrases that have well-known technical or construction industry meanings shall have such recognized meanings unless the context requires otherwise.
- D. Words used in the singular shall include the plural, and the plural the singular.
- E. Words used in the masculine gender shall include the feminine and the feminine the masculine.
- F. These rules of construction shall not apply to any part of the Contract that expressly excludes such construction, or where the subject matter or context of such provision requires otherwise.
- G. When the Contract Documents provide for a time determination by stating a certain number of days, the parties shall determine such time as follows:
  1. Exclude the first day and include the last day.
  2. Exclude Sunday if it would otherwise be the last day.
  3. Exclude the following Holidays as observed by the City if such Holiday would otherwise be the last day: Labor Day, Veteran's Day, Thanksgiving Day, Christmas Day, New Year's Day, President's Day, Memorial Day or Independence Day.
- H. Contract Documents frequently omit modifying words such as "all" and "any" and articles such as "the" and "an." Such omission in one statement as opposed to inclusion in another shall not affect the interpretation of either statement.

- I. The parties shall interpret the General Conditions exclusively according to the terms of the Contract Documents. The parties do not intend any comparison to any other document.

### III. OWNERSHIP AND USE OF DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS

- A. The Drawings, Specifications and other documents the Architect prepares for this Project are and shall remain the property of the City and the Architect. Both the City and the Architect retain all common law, statutory and other reserved rights, including any copyright.
- B. Upon completion of the Work, the Contractor shall return or account for all copies of any Drawings, Specifications and other documents the Architect prepares (except the Contractor's record set) to the Architect.
- C. The City and the Architect have provided the Drawings, Specifications and other documents the Architect prepares for this Project (and copies thereof furnished to the Contractor) solely for use in this Project. Any other use requires the specific written consent of the City and Architect. The Contractor, Subcontractor, Sub-subcontractor, and material or equipment suppliers, shall not use such documents on other projects, including additions to this Project outside the scope of the Work.
- D. The City and Architect hereby grant to the Contractor, Subcontractors, Sub-subcontractors and material or equipment suppliers a limited license to use and reproduce applicable portions of the Drawings, Specifications and other documents the Architect prepares for this Project. Subcontractors, Sub-subcontractors and material or equipment suppliers shall take such license limited strictly to documents appropriate for use in their own work. Such license shall include authority to submit or distribute licensed documents to meet official regulatory requirements or for other official purposes for the Project.

## **PRECONDITIONS AND ASSURANCES**

### IV. GENERAL PRECONDITIONS AND ASSURANCES

- A. By submitting a bid, the Contractor represents that the Contractor has:

1. Inspected and otherwise acquired site specific information of and concerning:
    - a. The conditions under which the work is to be performed;
    - b. the site of the work;
    - c. the structure of the ground;
    - d. any obstacles that may be encountered; and
    - e. all other relevant matters concerning the work;
  2. Compared and evaluated such personal observations with the requirements of the Contract Documents;
  3. Determined such methods and practices necessary as to underground structures, underground utilities (both public and private), underground soil and rock formations, ground water, and other obstacles that may be encountered;
  4. Made and prepared its Bid using only materials and equipment which comply fully with the plans and specifications, acknowledging that any failure to do so shall make the Contractor responsible for furnishing materials and equipment which fully conform without additional compensation;
  5. Examined the complete specifications and plans, including all related documents, all of which may contain provisions applicable not only to the Contractor, but also to the Subcontractors;
  6. Made such examinations and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the Contract;
  7. Verified the correctness of any quantities listed in any Contract Documents; and
  8. Received all the information the Contractor needs concerning the conditions of the Project Site.
- B. The Contractor shall not present a claim for adjustment to the Contract Sum or Contract Time for any condition the Contractor knew or reasonably should have known from information available to the contractor under Subparagraph IV(A). The Contractor shall not present a claim for surface or subsurface conditions encountered.
- C. The Contractor shall not present a claim for adjustment to the Contract Sum or Contract Time for any dispute related to: estimates of quantities in the Contract, or any misunderstanding of the nature or amount of work to be done.
- D. The Contractor shall employ such methods and means in the carrying out the work as will not cause any interruption or interference with any other contractor or subcontractor.
- E. Based upon the contract documents, the Contractor agrees and acknowledges that:
1. The Contract documents are adequate and sufficient to provide for completion of the Work. This acknowledgment extends to work that by inference or necessity may be required or useful for the completion of the work in accordance with all applicable laws, codes and professional



standards, even though such work may not be expressly provided for in the Contract Documents;

2. The contract sum is reasonable compensation for all the Work, including all unforeseen, foreseen and foreseeable risks, hazards and difficulties in connection with the Work;
3. The Contract Time is adequate for the performance of the Work; and
4. The Work shall not result in any lateral or vertical movement of any structure.

- F. The Contractor shall sign all necessary Contract Documents and any related documents necessary to complete the Work.

#### V. UNIT PRICES.

When the Contract Documents provide for portions or quantities of Work on a unit price basis, such estimated quantities in the Contract are approximate and are to be used only as a basis for estimating the probable cost of the work and for comparing the proposals offered for the work. The Contractor agrees that, during progress of the work, the City may find it advisable to increase or decrease the quantities as the City may deem necessary or desirable. The actual amount of work to be done and material to be furnished on a Unit Price basis may differ from the estimated quantities. The City shall make payment for Unit Price Work based on the actual number of units installed on the completed work.

#### VI. STATED CONDITIONS.

Where the City indicates conditions in the Contract Documents, such conditions shall be considered only for information and as indicative of conditions as observed at the time and place indicated. The City shall not be held responsible for any variance in conditions encountered at the time of actual work.

## CITY

#### VII. INFORMATION AND SERVICES REQUIRED OF THE CITY

- A. The City shall not be responsible for furnishing surveys (unless required for the execution of the work and requested by the Contractor in writing) or for providing other information as to the physical characteristics, legal limitations, or utility locations for the project site. The City shall furnish or cause to be furnished to the Contractor a

legal description of the project site. Such legal description shall not be a part of the Contract Documents. The City may provide existing test borings for the site. If the Contractor uses any such information, the Contractor is solely responsible for such use. The City does not assume any responsibility whatsoever as to the sufficiency or accuracy of such borings, or any logs or results from such borings including any related interpretations. Further, the City provides absolutely no warranty or guarantee, express or implied, that the conditions indicated by such borings, investigations, logs, or information are representative of those existing throughout the project site, or any part thereof, or that changes or unforeseen developments may not occur.

- B. Except for permits and fees that are the responsibility of the Contractor under the Contract Documents, (For example see: Paragraph XVIII.) the City shall secure and pay for necessary approvals, easements, assessments and charges required for construction, use or occupancy of permanent structures or for permanent changes in existing facilities.
- C. The City shall furnish information or services under the City's control with reasonable promptness to avoid delay in orderly progress of the Work.
- D. The above responsibilities supplement other duties and responsibilities of the City provided elsewhere, specifically including Construction by City or by Separate Contractors, Payments and Completion, and Insurance and Bonds.

#### VIII. CITY'S RIGHT TO STOP THE WORK

If the Contractor fails to correct Work that is not in accordance with the requirements of the Contract Documents (as required by correction of work provisions), or persistently fails to carry out Work in accordance with the Contract Documents, the City may order the Contractor to stop the Work, or any portion thereof, until the Contractor eliminates the cause for such order. The Mayor shall sign such stop order stating such cause in writing. The right of the City to stop the Work shall not give rise to a duty for the City to exercise this right for the Contractor or any other person or entity.

#### IX. CITY'S RIGHT TO CARRY OUT THE WORK

- A. If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents, the City may (without prejudice to other remedies) correct such deficiencies. The City may do so only when the Contractor fails to commence corrections within a seven-day period after receipt of written notice from the City, or when the Contractor fails to continue correction of such deficiencies with diligence and promptness.

- B. The City or the Architect shall issue an appropriate Change Order deducting the cost of correcting such deficiencies. Such Change Order shall include compensation for the Architect's additional services and expenses made necessary by such default, neglect or failure. If payments then or thereafter due to the Contractor are not sufficient to cover such amounts, the Contractor shall pay the difference to the City.

#### X. STORAGE OF MATERIALS

- A. The Contract shall store all materials under the general supervision and direction of the Architect.
- B. The Contractor shall store all Materials to preserve their quality and fitness for the Work and to facilitate prompt inspection.
- C. The Architect may, when needed, order the Contractor to store Materials under cover or on wooden platforms or as the Architect otherwise reasonably requires to protect the same from damage.
- D. The Contractor shall not use any materials in the Work that may contain Asbestos as defined under the Nebraska Asbestos Control Act, Neb. Rev. Stat §§71-6301 et. seq. without the express written approval of the City.

#### XI. ALTERATIONS AND SUBSTITUTIONS.

- A. The City or the Architect shall have the right to alter and modify the plans and specifications, thus making specific changes in the Work. If such changes diminish the amount of Work, the Contractor shall not file any claim for anticipated profit from such loss of Work. If such changes increase the amount of work, such increase shall be made by Modification to the Contract.
- B. Whenever the drawings or specifications identify a material, article, or piece of equipment by brand name or catalog number, such identification shall define performance, quality level, or other salient requirements. The Architect may consider other products of equal performance, capacity, quality and function upon the Contractor's written substitution request. Otherwise, the Contractor shall use the identified goods, unless the Architect approves such request for substitution in writing. Upon any substitution of lesser priced goods, the Architect shall prepare a Modification deducting any resulting price differential from the Contract Sum. Otherwise, the Contractor shall make any incidental changes or extra component parts required to accommodate the substitute without a change in the

Contract Sum or Contract Time. The Contractor warrants that approved substitutes will not effect major changes in the function or general design.

#### XII. DEFECTIVE MATERIALS.

- A. The City shall consider all materials not conforming to the specifications as defective. Unless remedied, the City shall reject all defective material, whether in place or not. The Contractor shall remove any such defective material from the work site at the Contractor's own cost.
- B. The Architect may approve materials the Contractor has remedied by reconditioning or correction to satisfactorily meet the Specifications. The Architect may make such approval in writing upon the written request of the Contractor. The Contractor shall not use any remedied materials without such written approval.

#### XIII. CITY SUPPLIED MATERIALS.

- A. The City shall furnish City supplied Material or equipment according to the Contract Documents in good condition and ready for installation. The Contractor shall pick up such material or equipment at a location the City or the Architect shall designate.
- B. The Contractor shall inspect and measure all City supplied material or equipment before the same is loaded onto the Contractor's vehicle for transportation to the work site. The Contractor shall complete and sign a Certificate of Acceptance for such materials and immediately submit the same to the Architect or his authorized representative. The Contractor shall note all defects in materials and measure on such Certificate.
- C. The Contractor shall return any excess city supplied materials to the point of receipt. The City shall thereupon issue the Contractor a written receipt verifying condition and measures such excess material. The City may refuse any materials damaged by the Contractor. The Contractor shall pay for the cost of any such damaged materials.

### CONTRACTOR

#### XIV. REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR

- A. The Contractor hereby specifically acknowledges and declares that the Contract Documents are complete and sufficient to have enabled the Contractor to determine the cost of the work. The Contractor hereby specifically acknowledges and declares that

the Drawings, Specifications and all addenda are sufficient to enable the Contractor to construct the Work in accordance with applicable laws, statutes, building codes and regulations, and otherwise to fulfill all its obligations to complete the Work. In addition, if the Contractor performs any construction activity with knowledge that it involves a recognized error, inconsistency or omission in the Contract Documents, the Contractor shall assume full responsibility for such performance and shall bear the attributable costs for correction. See Subparagraph XVIII(C) for discrepancies related to Building Codes and regulations.

- B. The Contractor shall take field measurements and verify field conditions and shall carefully compare such field measurements and conditions and other information known to the Contractor with the Contract Documents before commencing activities. The Contractor shall immediately report any errors, inconsistencies or omissions discovered to the Architect in writing.
- C. The Contractor shall perform the Work in accordance with the Contract Documents and submittals approved pursuant to Paragraph XXIV.
- D. The Architect or City may furnish the Contractor additional instructions and detailed drawings as necessary to carry out the Work. Such additional drawings are a part of the Contract Documents

#### **XV. SUPERVISION AND CONSTRUCTION PROCEDURES**

- A. The Contractor shall supervise and direct the Work, using the Contractor's best skill and attention. The Contractor shall be solely responsible for and shall have control over construction means, methods, techniques, sequences, coordination, and procedures for all portions of the Work.
- B. The Contractor shall be responsible to the City for acts and omissions of the Contractor's employees, Subcontractors and their agents and employees, and other persons performing portions of the Work under a contract with Contractor.
- C. The Contractor shall not be relieved of obligations to perform the Work in accordance with the Contract Documents either by activities or duties of the Architect in the Architect's administration of the Contract, or by tests, inspections or approvals persons other than the Contractor perform.

- D. The Contractor shall be responsible for inspection of portions of Work already performed under this Contract to determine that such portions are in proper condition to receive subsequent Work.
- E. At the earliest possible time after the commencement of the Work on the Project Site, the Contractor shall:
  - 1. Contract (at Contractor's expense) a state licensed land surveyor to verify and establish all property corners and benchmarks;
  - 2. Locate the Project on the Project Site;
  - 3. Establish any necessary reference marks and axes from which the Work accurately can progress;
  - 4. Furnish the Architect evidence of the verification required above; and
  - 5. Provide written Notice to the City of any errors discovered from such verification.
- F. If the Work requires any public authority to inspect or approve the same, the Contractor shall cause the timely performance of any such inspection or approval. No such inspection performed or failed to be performed shall waive the Contractor's obligations under the Contract Documents. No such inspection or approval (even if the City is the inspecting or approving authority) shall act as an approval or acceptance of the Work or portions thereof by the City.
- G. The Contractor acknowledges that it is the Contractor's responsibility to hire all personnel for the proper and diligent prosecution of the Work. The Contractor shall use its best efforts to maintain labor peace for the duration of the Work. In the event of a labor dispute, the Contractor shall not be entitled to any increase in the Contract Sum.

#### **XVI. LABOR AND MATERIALS**

- A. Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for: labor, materials, equipment, tools, construction equipment and machinery; water, heat, utilities, transportation, and other facilities; and any other item or services necessary for proper execution and completion of the Work. Such items and services shall be so provided regardless of whether temporary or permanent or whether incorporated or to be incorporated in the Work.
- B. The Contractor shall enforce strict discipline and good order among the Contractor's employees and other persons carrying out the Contract. The Contractor shall not employ or permit employment of unfit persons or persons not skilled in tasks assigned to them.

---

**XVII. WARRANTY**

- A. The Contractor warrants to the City that:
  - 1. Materials and equipment furnished under the Contract shall be of good quality and new unless otherwise required or permitted by the Contract Documents;
  - 2. The Work shall be free from defects not inherent in the quality required or permitted;
  - 3. The Work shall be performed in accordance with accepted and established practices and procedures recognized in the construction trade in general and the Architect or design professionals in general; and
  - 4. The Work shall conform with the requirements of the Contract Documents.
- B. The City may consider Work not conforming to these warranty requirements as defective Work.
- C. The Contractor's warranty excludes: Remedy for damage caused by abuse by the City; Modifications not executed by the Contractor; improper or insufficient maintenance by the City; improper operation by the City; or normal wear and tear under normal usage.

---

**XVIII. PERMITS, FEES AND NOTICES**

- A. Unless specifically exempted in the Contract Documents, the Contractor shall secure and pay for the building permit and other legally required permits and governmental fees, licenses and inspections necessary for proper execution and completion of the Work that are customarily secured after execution of the Contract. The Contractor shall procure all Certificates of inspection, use, occupancy, permits and licenses, pay all charges and fees and give all notices necessary and incidental to the due and lawful prosecution of the Work. Certificates of inspection, use, or occupancy shall be delivered to the City upon completion of the Work. Such delivery shall be made in a timely manner to allow the City to occupy the Project in accordance with the approved Work schedule. The Contractor shall not request or claim any adjustment to the Contract Sum for the costs of procuring any such inspections or approvals.
- B. The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on performance of the Work and shall likewise require all subcontractors and all their employees to do the same.

- C. The Contractor shall review the Contract Documents to determine any discrepancy between building codes and regulations the Contractor has knowledge of or should reasonably be able to determine. The Contractor shall immediately notify the City and the Architect in writing of any such discrepancies. The Contractor shall not violate any zoning, setback or other location requirements, laws or codes and ordinances, or of any recorded covenants the Contractor has knowledge. If the Contractor observes that portions of the Contract documents are at variance with applicable laws, statutes, ordinances, building codes, rules or regulations, the Contractor shall promptly notify the City and the Architect in writing, and any resulting changes necessary shall be accomplished by appropriate Modification. See Subparagraph XIV(A) for discrepancies related to error, inconsistency or omission in the Contract Documents.
- D. If the Contractor performs Work knowing it to be contrary to laws, statutes, ordinances, building codes, and rules and regulations without such notice to the Architect and City, the Contractor shall assume full responsibility for such Work. In addition, the Contractor shall bear the attributable costs of correction.

---

**XIX. PRE-CONSTRUCTION AND PROGRESS CONFERENCES.**

- A. Within forty-eight (48) hours of receipt of notification from the Architect, the Contractor or his authorized representative shall, at no cost to the City, appear at a location designated by the Architect for the purpose of discussing pre-construction or construction scheduling, traffic control procedure or methods, and project progress during construction.
- B. At such conferences the Contractor or his authorized representative shall provide, at no cost to the City, any data sheets, construction schedules, or other information the Architect may reasonably request.

---

**XX. ALLOWANCES**

- A. The Contractor shall include in the Contract Sum all allowances stated in the Contract Documents. The Contractor shall supply items covered by allowances in such amounts and by such persons or entities as the City may direct. The Contractor may make reasonable objection to employing such persons or entities. Upon such reasonable objection the City shall appoint or direct alternate persons or entities as needed.
- B. Unless otherwise provided in the Contract Documents:
  - 1. The City shall select Materials and equipment under any allowance to avoid delay in the Work;

2. To determine Allowances, the Contractor shall include the Contractor's cost for materials and equipment delivered at the site and all required taxes, less applicable trade discounts;
3. The Contract Sum (not the related allowances) shall include the Contractor's costs for unloading and handling at the site, labor, installation costs, overhead, profit and other expenses related to such allowances.
4. Whenever the costs in Clause XX(B)(2); above are more than or less than allowances, the City and Contractor shall adjust the Contract Sum accordingly by Change Order.

---

**XXIII. DOCUMENTS AND SAMPLES AT THE SITE**

The Contractor shall maintain at the site for the City one record copy of the Drawings; Specifications; Addenda; Change Orders; Modifications; approved Shop Drawings; Product Data, Samples and similar required submittals in good order and marked currently to record changes and selections made during construction. During the Work, The Contractor shall permit the City and Architect access to such record copy. The Contractor shall deliver the same to the City upon completion of the Work.

---

**XI. SUPERINTENDENT**

The Contractor shall employ a competent superintendent and necessary assistants who shall be in attendance at the Project site during the Work. The superintendent shall represent the Contractor. Any Communication to the superintendent or that the superintendent receives shall bind the Contractor. The City or Architect shall confirm important communications to the Contractor in writing. The City or Architect shall similarly confirm any specific communication upon the written request of the Contractor.

---

**XXII. CONTRACTOR'S CONSTRUCTION SCHEDULES**

- A. The Contractor, promptly after being awarded the Contract, shall prepare and submit for the City's and Architect's information a Contractor's construction schedule for the Work. The schedule shall not exceed time limits current under the Contract Documents. The Contractor shall revise the same at appropriate intervals as required by the conditions of the work and Project. The Contractor shall relate such schedules to the entire Project for the expeditious and practicable execution of the Work.
- B. The Contractor shall prepare and keep current, for the Architect's approval, a schedule of submittals. The Contractor shall coordinate such schedule with the Contractor's construction schedule. The Contractor shall submit the same to the Architect allowing the Architect reasonable time to review the submittals.
- C. The Contractor shall conform to the most recent schedules.

---

**XXIV. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES**

- A. Contract Documents shall not include Shop Drawings, Product Data, Samples and similar submittals. Such submittals demonstrate or illustrate the Contractor's proposal to conform to the information given and the design concept expressed in the Contract Documents for related portions of the Work.
- B. The Contractor shall review, approve, and submit to the Architect any Shop Drawings, Product Data, Samples, and similar submittals the Contract Documents require. The Contractor shall do so with reasonable promptness to prevent any delay in the Work or in the activities of the City or of separate contractors. The Architect may return (without any further action) any Submittals that the Contract Documents do not require.
- C. The Contractor shall obtain the Architects approval before beginning any portion of the Work requiring submittal and review of Shop Drawings, Product Data, Samples or similar submittals. The Contractor shall perform such Work only in accordance with approved submittals.
- D. By approving and submitting Shop Drawings, Product Data, Samples and similar submittals, the Contractor represents that the Contractor has determined and verified materials, field measurements and field construction criteria related thereto, and has checked and coordinated the information contained within such submittals with the requirements of the work and the Contract Documents.
- E. The Architect's approval of such submittals shall not excuse the Contractor for deviations from any requirements of the Contract Documents. The obtain specific written approval for such deviations only when the Contractor has given written notice to the Architect with the original submittal and the Architect and the City have given written approval to the specific deviation. The Architect's approval of such submittals shall not relieve the Contractor from responsibility for any errors or omissions therein.

- F. The Contractor shall direct specific attention, in writing or on resubmitted Shop Drawings, Product Data, Samples or similar submittals, to revisions other than revisions the Architect requested on previous submittals.
- G. The Contractor may identify Informational submittals in the Contract Documents that the Architect is not expected to respond to or approve.
- H. When the Contract Documents require professional certification of performance criteria of materials, systems or equipment, the City and the Architect shall be entitled to reasonably rely upon the accuracy and completeness of such calculations and certifications.

---

**XXV. USE OF SITE**

- A. The Contractor shall confine operations at the site to areas permitted by law, ordinances, permits and the Contract Documents. The Contractor shall not unreasonably encumber the site with materials or equipment.
- B. The Contractor shall protect the site and the Work from loss by theft or otherwise. Until completion and final acceptance of the work, the Contractor shall assume all risks for repair and replacement for damage to the site and the Work, whether caused by lightning, fire, wind, water, theft, vandalism or other causes.

---

**XXVI. CONTRACTOR'S USE OF UTILITIES.**

- A. The Contractor shall arrange for all temporary service connections for various utilities and shall pay the various utilities for such temporary services.
- B. Prior to the use of any City water from a fire hydrant, the Contractor shall take out the necessary permit for a hydrant meter and valve from the Lincoln Water System.
- C. The Contractor shall pay the permit fees that are established by the Lincoln Water System for the installation or moving of hydrant meters and valves.
- D. The Contractor shall not operate the hydrant, but may use the exterior valve to control the flow of water. The Contractor shall be liable for any damage to the meter and valve.

---

**XXVII. CUTTING AND PATCHING**

- A. The Contractor shall be responsible for cutting, fitting or patching required to complete the Work or to make parts of the Work fit together properly.

- B. The Contractor shall not damage or endanger any portion of the Work or fully or partially completed construction of the City or separate contractors by cutting, patching or otherwise altering such construction, or by excavation. The Contractor shall not cut or otherwise alter such construction by the City or a separate contractor except with written consent of the City and of such separate contractor. Such consent shall not be unreasonably withheld. The Contractor shall not unreasonably withhold from the City or a separate contractor the Contractor's consent to cutting or otherwise altering the Work.

---

**XXVIII. CLEANING UP**

- A. The Contractor shall keep the premises and surrounding area free from accumulation of waste materials or rubbish caused by operations under the Contract. At completion of the Work the Contractor shall remove from and about the Project, all waste materials, rubbish, tools, construction equipment, machinery and surplus materials.
- B. If the Contractor fails to clean up as provided in the Contract Documents, the City may do so and charge the cost thereof to the Contractor.

---

**XXIX. ACCESS TO WORK**

The Contractor shall provide the City and Architect access to the Work in preparation and progress wherever located.

---

**XXX. ROYALTIES AND PATENTS**

- A. It is mutually understood and agreed that, without exception, the Contract Sum includes all royalties and costs arising from patents, trademarks, and copyrights in any way involved in the Work.
- B. Whenever the Contractor uses or the Contract Documents require any design device, material, or process covered by letters, patent, or copyright, the Contractor shall provide for the right for such use by legal agreement with the patentee or owner thereof. Regardless of any agreement or lack thereof, the Contractor and the surety in all cases shall indemnify and hold harmless the City from any and all claims for infringement by the use of any such patented design, device, material, process, trademark or copyright, in connection with the Work. Likewise, the Contractor and the surety in all such cases shall indemnify the City for any costs, expenses, and damages that the City may be obligated to pay, for any such claims. The indemnification provided herein shall apply at any time during the Work and shall continue after the completion of the work indefinitely.

- C. The Contractor shall pay all royalties and license fees.
- D. The Contractor shall defend suits or Claims for infringement of patent rights.
- E. The Contractor shall promptly notify the Architect of any required design, process, or product the Contractor has reason to believe is an infringement of a patent, copyright or other intangible right. The Contractor shall assume full responsibility for and shall bear the attributable costs for any possible patent, copyright or other alleged infringement of intangible rights.

---

**XXXI. INDEMNIFICATION**

- A. To the fullest extent permitted by law, the Contractor shall indemnify and Hold Harmless the City, Architect, and agents and employees of any of them from and against Claims, damages, losses and expenses, including but not limited to attorneys' fees, arising out of or resulting from performance of the Work, that results in any Claim for damage whatsoever, including without limitation, any bodily injury, sickness, disease, death, or any injury to or destruction of tangible or intangible property, including any loss of use resulting therefrom that is caused in whole or in part by Contractor or anyone directly or indirectly employed by Contractor, or anyone for whose acts any of them may be liable, regardless of whether or not such Claim, damage, loss or expense is caused in part by a party indemnified hereunder. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity that would otherwise exist as to a party or person described in this Paragraph XXXI. This section shall not require Contractor to indemnify or Hold Harmless the City for any losses, Claims, damages, and expenses arising out of or resulting from the sole negligence of the City.
- B. In addition, the City shall not be responsible nor be held liable, for any damage consequent upon the use, misuse or failure of any equipment used by Contractor or anyone directly or indirectly employed by Contractor. The Contractor's acceptance or use of any such equipment shall mean that Contractor accepts full responsibility for any loss or damage to the equipment while the equipment was used or under the control of Contractor, or anyone directly or indirectly employed by Contractor. In addition to paying for any such damage to the equipment itself, the Contractor agrees to exonerate, indemnify, and hold harmless the City from and against any and all Claims for any damage whatsoever resulting from the use, misuse or failure of such equipment. Such indemnification applies

regardless of whether such damage or loss is occasioned by any employee or property of Contractor, the City or other persons. Such indemnification shall not be qualified or reduced in any way because the subject equipment may be furnished, rented or loaned to Contractor by the City.

- C. In Claims by any person or entity indemnified under this Paragraph XXXI or by an employee of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, the indemnification obligation under this Paragraph XXXI shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or a Subcontractor under workers' or worker's compensation acts, disability benefit acts or other employee benefit acts.

---

**XXXII. PROTECTION OF WORK AND PROPERTY**

- A. The Contractor shall protect and support all water, sewer, gas and other pipes and structures; telephones, telegraph or electric power lines; all railroad tracks, pavement, building walls, fences, utilities, or other properties, public or private, which may be damaged during the execution of this Work. During all operations under the Contract, the Contractor shall carefully protect all trees, shrubbery, sod, plantings, etc., not designated to be removed as part of the work of the Contract.
- B. In the event of damage or injury to such property or improvements, the Contractor shall promptly repair the same to the satisfaction of the City. The Contractor shall pay the attributable costs for any such repairs. See Also: Contractor's obligations and assumption of risk in Subparagraph XXV.
- C. The City may provide information for existing sub-surface structures in the vicinity of the work in the Contract Documents. The City does not, however, guarantee the completeness or accuracy of this information. Any delay or extra cost to the Contractor due to encountering structures differing from those provided shall not constitute a Claim for extra payment.

---

**XXXIII. TRAFFIC CONTROL**

- A. Where required for any activities related to the Work, all Traffic Control Devices and Signs shall conform to the City's traffic control regulations and requirements.
- B. All costs associated with traffic control shall be paid for by the Contractor as a part of the Contract Sum.

---

**XXXIV. FAIR EMPLOYMENT PRACTICES**

The Contractor and the Subcontractors shall not discriminate against any employee (or applicant for employment) with

respect to compensation, terms, advancement potential, conditions, or privileges of employment, because of such person's race, color, religion, sex, disability, national origin, ancestry, age, or marital status pursuant to the requirements of Lincoln Municipal code Chapter 11.08 and Section 48-1122, Nebraska Reissue Revised Statutes of 1943.

#### XXXV. FAIR LABOR STANDARDS

The Contractor and the Subcontractors shall maintain Fair Labor Standards in the performance of the Contract, as required by Chapter 73, Nebraska Reissue Revised Statutes of 1943.

## ARCHITECT

#### XXXVI. ARCHITECT'S ADMINISTRATION OF THE CONTRACT

- A. The Architect shall provide administration of the Contract as described in the Contract Documents, and may act as the City's representative, with the City's concurrence, (1) during construction, (2) until final payment is due and (3) from time to time during the correction period described in Paragraph LXIV. The Architect shall have authority to act on behalf of the City only to the extent provided in the Contract Documents and allowed by law.
- B. The City and the Architect shall at all times have the right of access to the site. The City requires the Architect to visit the site at intervals appropriate to the stage of construction to become generally familiar with the progress and quality of the completed Work and to determine if the Work is being performed in a manner that, when completed, will be in accordance with the Contract Documents. On the basis of on-site observations, the City requires the Architect to keep the City informed of progress of the Work, and guard the City against defects and deficiencies in the Work. The Contractor shall cooperate and accommodate the Architect pursuant to the site visitation and reporting requirements above. The Architect's responsibilities shall not lessen or excuse any obligations or duties of the Contractor.
- C. The City and Contractor shall attempt to communicate to each other through the Architect. The City and Contractor shall communicate with the Architect's consultants through the Architect. The City shall communicate with

Subcontractors and material suppliers through the Contractor. The Contractor shall communicate with separate contractors through the City.

- D. The Contractor shall permit the Architect to review and certify any amounts Claimed due upon observation and evaluation of the Contractor's Applications for Payment. The Architect shall issue certificates for Payment to the City based on such review.
- E. The Architect may reject Work that does not conform to the Contract Documents. Whenever the Architect considers it necessary or advisable for implementation of the intent of the Contract Documents, the Architect may require additional inspection or testing of the Work in accordance with Subparagraphs LXII(A-B), whether or not such Work is fabricated, installed or completed. However, neither this authority of the Architect nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the Architect to the Contractor, Subcontractors, material and equipment suppliers, their agents or employees, or other persons performing portions of the Work other than the City.
- F. The Architect shall review and approve or take other appropriate action upon the contractor's submittals such as Shop Drawings, Product Data and Samples. The Architect shall review the same for conformance with information given and the design concept expressed in the Contract Documents. The Architect's review shall not excuse the Contractor from determining the accuracy and completeness of details such as dimensions and quantities, or for substantiating instructions for installation or performance of equipment or systems. The Architect's review of the Contractor's submittals shall not relieve the Contractor of the obligations under Paragraphs XIV, XVII, and XXIV. The Architect's review shall not constitute approval of safety precautions or any construction means, methods, techniques, sequences or procedures (unless otherwise specifically stated by the Architect.) The Architect's approval of a specific item shall not indicate approval of an assembly of which the item is a component.
- G. The Contractor shall permit the Architect to conduct inspections to determine the date or dates of Substantial Completion and the date of final completion.
- H. If the City and Architect agree, the Architect may provide one or more project representatives to assist in carrying out the Architect's responsibilities at the site. The duties, responsibilities and limitations of authority of such project representatives shall be as set forth in an exhibit to be incorporated in the Contract Documents.



## **CLAIMS & DISPUTES**

### **XXXVII. CLAIMS AND DISPUTES**

- A. The Contractor and City shall make any Claim against the other party in writing giving a description thereof to the Architect and the other party. The claimant may make a Claim only within 21 days after occurrence of the event giving rise to such Claim or within 21 days after the Claimant first recognizes the condition giving rise to the Claim, whichever is later.
- B. Pending final resolution of a Claim (unless the Parties otherwise agree in writing) the Contractor shall proceed diligently with performance of the Contract and the City shall continue to make payments in accordance with the Contract Documents.
- C. When the City makes final payment and the Contractor accepts the same, the City and the Contractor thereby waive all claims except those arising from:
  - 1. Unsettled liens, Claims, security interests or encumbrances arising out of the Contract;
  - 2. Failure of the Work to comply with the requirements of the Contract Documents; or
  - 3. Terms of special warranties required by the Contract Documents.
- D. If the either party encounters or discovers (1) subsurface or otherwise concealed physical conditions which differ materially from the Contract Documents or (2) unknown physical conditions of an unusual nature, which differ materially from those ordinarily found to exist and generally recognized as inherently encountered in the Work, then the observing party shall give prompt notice of the condition to the Architect and the other party by giving a description thereof. The observing party shall give such notice promptly before conditions are disturbed and in no event later than 21 days after first observance of the same.
- E. If the Contractor wishes to make Claim for an increase in the Contract Sum, the Contractor shall provide written notice as provided herein before proceeding to execute the Work. notice is not required for Claims relating to an emergency endangering life or property arising under Paragraph LVIII, Emergencies. The Contractor may make claims for additional cost for reasons including but not limited to (1) a written opinion from the Architect, (2) an order by the City to stop the Work where the Contractor was not at fault, (3) a written order for a minor change in the Work issued by the Architect, (4) failure of payment

by the City, (5) termination of the Contract by the City, (6) City's suspension or (7) other reasonable grounds.

- F. If the Contractor wishes to make Claim for an increase in the Contract Time, the Contractor shall give written notice as provided herein. The Contractor's Claim shall include an estimate of cost and delay on the Work, if any. In the case of a continuing delay only one Claim is necessary.
- G. If the Contractor bases a Claim for additional time on adverse weather, the Contractor shall substantiate such Claim with data substantiating that: (1) the adverse weather was abnormal for the period of time, (2) the Contractor could not have reasonably anticipated the adverse weather, and (3) the weather had an adverse effect on the scheduled construction.
- H. If either party to the Contract suffers injury or damage to person or property because of an act or omission of the other party, of any of the other party's employees or agents, or of others for whose acts such party is legally liable, the claimant shall give written notice of such injury or damage (whether or not insured) to the other party within 21 days after first observance. The notice shall provide sufficient detail to enable the other party to investigate the matter. If the claimant asserts additional cost or time related to such injury or damage, the claimant shall file a separate claim for each.

### **XXXVIII. RESOLUTION OF CLAIMS AND DISPUTES**

- A. The Architect shall review Claims and take one or more of the following preliminary actions within ten days after receipt of a Claim: (1) request additional supporting data from the Claimant, (2) submit a schedule to the parties indicating when the Architect expects to take action, (3) reject the Claim in whole or in part, stating reasons for rejection, (4) recommend approval of the Claim by the other party or (5) suggest a compromise. The Architect may also, but is not obligated to, notify the surety, if any, of the nature and amount of the Claim.
- B. If the City and Contractor resolve the Claim, the Architect shall prepare a Change Order or other documentation accordingly.
- C. If the City and Contractor do not resolve the Claim after consideration of the foregoing, either party may seek a judicial resolution of any Claim. Any Claim against the City shall comply with the provisions of Neb. Rev. Stat. 15-840 et seq. and other applicable laws relating to claims against the City.

## **SUBCONTRACTORS**

### **XXXIX. AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK**

- A. The Contractor shall notify the Architect of the names and addresses of the Subcontractors (including those who are to furnish materials or equipment fabricated to a special design) the Contractor proposes to use on the contract. The Contractor shall submit such notification before beginning any subcontracted work.
- B. Nothing contained in the Contract Documents shall create any contractual relationship between any Subcontractor and the City. The Contractor agrees to be fully responsible to the City for the acts or omissions of Subcontractors and of anyone employed directly or indirectly by the Contractor or Subcontractors. This contract obligation shall be in addition to the liability imposed by law upon the Contractor.
- C. The Contractor agrees to bind every Subcontractor (and every Subcontractor of a Subcontractor) by the terms of the General Conditions and the Special Provisions of the contract, plans, and specifications as far as applicable, including insurance requirements, unless specifically noted to the contrary in a subcontract the City has approved in writing.
- D. The Contractor shall not contract with a proposed Subcontractor to whom the City or Architect has made reasonable and timely objection. The Contractor shall not be required to contract with anyone to whom the Contractor has made reasonable objection.
- E. If the City or Architect has reasonable objection to a Subcontractor proposed by the contractor, the Contractor shall propose another to whom the City or Architect has no reasonable objection. The Contract Sum shall be increased or decreased by the difference in cost occasioned by such change and an appropriate Change Order shall be issued. However, no increase in the Contract Sum shall be allowed for such change unless the Contractor has acted promptly and responsively in submitting names as required.
- F. The Contractor shall not change a Subcontractor previously selected if the City or Architect makes reasonable objection to such change.
- G. Failure of the City or Architect to reply within ten days after a subcontractor's submittal for approval shall mean the City has no reasonable objection.
- H. By appropriate written agreement, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound by terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities that the Contractor, by these Documents, assumes toward the City or Architect. Each subcontract agreement shall preserve and protect the rights of the City and Architect under the Contract Documents for each Subcontractor's Work so that subcontracting thereof shall not prejudice such rights. Such agreements shall allow to the Subcontractor (unless specifically provided otherwise in the subcontract agreement) the benefit of all rights, remedies and redress against the Contractor that the Contractor, by the Contract Documents, has against the City. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors. The Contractor shall make available to each proposed Subcontractor, prior to the execution of the subcontract agreement, copies of the Contract Documents to which the Subcontractor shall be bound. Upon written request of the Subcontractor, the Contractor shall identify to the Subcontractor terms and conditions of the proposed subcontract agreement that may be at variance with the Contract Documents. Subcontractors shall similarly make copies of applicable portions of such documents available to their respective proposed Sub-subcontractors.
- I. Notwithstanding any provision of Subparagraph XXXIX(A), the Contractor shall require a written Subcontract between the Contractor and such Subcontractor (or the Subcontractor and its Sub-subcontractor at any tier) for any part of the Work a Subcontractor or Sub-subcontractor performs. The Contractor shall use or require the use of a form of subcontract satisfactory to the City in all respects for such written agreements. Each such contract shall contain provisions that require the Subcontractor to:
  1. Perform such Work in accordance with the Contract Documents;
  2. Waive all rights the contracting parties may have against one another or that the Subcontractor may have against the City for damages caused by fire or other perils covered by insurance required in contract documents.
  3. Carry and maintain insurance coverage in accordance with the Contract Documents, and to file Certificates of such coverage with the Contractor;
  4. Submit to Contractor or Subcontractor, as the case may be, applications for payment (on a City approved form) together with clearly defined invoices and billings supporting all such applications under each subcontract;
  5. Report, so far as is practicable, unit prices and any other feasible formula for use in determination of the costs of changes in the Work;
  6. Furnish to the Contractor in a timely fashion all information necessary for the preparation and submission of the reports required in the Contract Documents;

7. Continue to perform under its subcontract in the event the Contract is terminated and the City shall take assignment of said contract and request such subcontractor to continue such performance;
8. Remove all debris created by its activities; and
9. Follow Fair Employment Practices and Fair Labor Standards.

---

**XL. CONTINGENT ASSIGNMENT OF SUBCONTRACTS**

- A. The Contractor shall automatically assign to the City each subcontract agreement the City accepts by notifying the Subcontractor in writing upon the City's termination of the Contract for cause pursuant to Paragraph LXXIII. Such assignment shall be subject to the prior rights of the surety, if any.
- B. If the Work has been suspended for more than 30 days, the City may equitably adjust compensation for any Subcontractor assigned hereunder.

## **CHANGES IN THE WORK**

---

**XLI. CHANGES**

- A. The City or Contractor may accomplish Changes in the Work after execution of the Contract (without invalidating the Contract) by Change Order, Construction Change Directive or order for a minor change in the Work (subject to the limitations stated in Changes In The Work (XLI - XLII) and elsewhere in the Contract Documents.)
- B. The parties shall perform Changes in the Work as provided in the Contract Documents, and the Contractor shall proceed promptly so as to avoid any delay in the Work, unless otherwise provided in such change in the Work.

---

**XLII. CONSTRUCTION CHANGE DIRECTIVES**

- A. The City may use A Construction Change Directive in the absence of total agreement on the terms of a Change Order.
- B. If the Construction Change Directive provides for an adjustment to the Contract Sum, the City shall calculate such adjustment based on one of the following methods:
  1. lump sum properly itemized and supported by sufficient substantiating data to permit City evaluation;

2. unit prices stated in the Contract Documents or subsequently agreed upon;
3. cost (to be determined in a manner the parties agree upon) plus a mutually acceptable fixed or percentage fee; or
4. as provided in Subparagraph XLII(E).

- C. Upon receipt of a Construction Change Directive, the Contractor shall promptly proceed with the change in the Work involved and advise the Architect of the Contractor's agreement or disagreement with the method, if any, provided in the Construction Change Directive for determining the proposed adjustment in the Contract Sum or Contract Time.
- D. If the Contractor signs such Construction Change Directive, such signature shall conclusively establish the agreement of the Contractor therewith, including adjustment in Contract Sum and Contract Time or the method for determining the same. The City shall consider such agreement as immediately effective and shall record such agreement as a Change Order.
- E. If the Contractor does not respond within 10 days or disagrees with the method for adjustment in the Contract Sum, the City shall determine the method and the adjustment on the basis of reasonable expenditures and savings of those performing the Work attributable to the change. In case of an adjustment that increases the Contract Sum, the expenditures attributable to the change shall include a reasonable allowance for overhead and profit. In such case, and under Clause XLII(B)(3), the Contractor shall keep and present (in such form as the City may prescribe) an itemized accounting together with appropriate supporting data. Unless otherwise provided in the Contract Documents, the City shall pay costs limited only to the following costs directly attributable to the change:
  1. Labor, including social security, old age and unemployment Insurance, fringe benefits required by agreement or custom, and workers' or workmen's compensation Insurance;
  2. Materials, supplies and equipment, including cost of transportation, whether incorporated or consumed;
  3. Rents for machinery and equipment, exclusive of hand tools, whether rented from the Contractor or others;
  4. Premiums for all Bonds and Insurance, permit fees, and sales, use or similar taxes related to the Work; and
  5. Additional supervision and field office personnel.
- F. Pending final determination of costs, the Contractor may include amounts not in dispute in Applications for Payment. For a deletion or change that results in a net decrease in the Contract Sum, the City and Contractor shall use the actual net cost to determine such decrease. When both additions and credits covering related Work or substitutions are involved in a change, the City and Contractor shall figure an allowance for overhead and profit on the basis of net increase, if any, with respect to that change.

- G. When the City and Contractor agree with the adjustments in the Contract Sum and Contract Time, or otherwise reach agreement upon the adjustments, such agreement shall be effective immediately. Such agreement shall be recorded by preparation and execution of an appropriate Change Order.

## **TIME**

### **XLIII. PROGRESS AND COMPLETION**

- A. Time limits stated in the Contract Documents are of the essence of the Contract. By executing the Contract the Contractor confirms that the Contract Time is a reasonable period for performing the Work.
- B. The Contractor shall not knowingly commence operations on the site or elsewhere prior to the effective date of Insurance required by Paragraphs LIX, LX, LXI, Insurance and Bonds. The effective date of such Insurance shall not change The Work Commencement Date in any event. The Contractor shall notify the City in writing not less than five days before commencing the Work unless the City establishes a different date of commencement by a notice to proceed.
- C. The Contractor shall proceed expeditiously with adequate forces and shall achieve Substantial Completion within the Contract Time.

### **XLIV. DELAYS AND EXTENSIONS OF TIME**

- A. If the Contractor is delayed by an act or neglect of the City or Architect, or of an employee of either, or of a separate contractor employed by the City, or by delay the City has authorized in writing, or by other causes that the City determines may justify delay, then the City and Contractor shall extend the Contract Time accordingly by Change Order.
- B. The Contractor shall make such claims in accordance with applicable provisions of Paragraph XXXVII.

### **XLV. LIQUIDATED DAMAGES**

- A. If the Contractor fails to complete the Work prior to the completion date (allowing for any approved extensions of time), the Contractor shall pay Liquidated Damages for each day that the work remains incomplete. The City shall deduct the amount of Liquidated Damages due from the money due the Contractor prior to final payment. If the

remaining amount due the Contractor is less than the total amount of Liquidated Damages, the Contractor shall pay the difference within 10 days. If the Contractor fails to pay such difference, the City shall have the right to recover the difference from the Contractor or his Surety.

- B. Unless specifically amended or modified by special provision, the daily amount of the Liquidated Damages shall be as follows:
1. Contract Sum up to and including \$100,000:  
\$100/day
  2. Contract Sum more than \$100,000 up to and including \$500,000:  
\$200/day
  3. Contract Sum more than \$500,000 up to and including \$1,000,000  
\$300/day.
  4. Contract Sum more than \$1,000,000  
\$400 /day.
- C. The Liquidated Damages provided herein are not considered punitive. The Contractor agrees that such damages are predetermined and reasonable amounts to compensate for the detriment to the public and to defray expenses incurred by the City due to the delay in the completion of the project.

## **PAYMENTS AND COMPLETION**

### **XLVI. CONTRACT SUM**

- A. The Contract Sum stated in the Contract (including any adjustments the City authorizes) is the total amount the City shall pay to the Contractor for the Work.
- B. Notwithstanding any other provision of the Contract Documents, the City may withhold any payment to the Contractor hereunder if and for so long as the Contractor fails to perform any of its obligations hereunder or if the Contractor is in default under any terms and conditions of the Contract Documents. Such withholding shall be limited to an amount, sufficient in the reasonable opinion of the City, to cure any such default or failure.

### **XLVII. SCHEDULE OF VALUES**

Before the first Application for Payment, the Contractor shall submit to the Architect and the City a schedule of values allocated to various portions of the Work, prepared in such form and supported by such data to substantiate its accuracy as the Architect may require. Upon agreement, the City and Architect shall use such schedule as a basis for reviewing the Contractor's Applications for Payment.

**XLVIII. APPLICATIONS FOR PAYMENT**

- A. At least ten days before the date established for each progress payment, the Contractor shall submit to the Architect and the City an itemized Application for Payment for completed operations. Such application shall be notarized and supported by such data substantiating the Contractor's right to payment as the City or Architect may require (such as copies of requisitions from Subcontractors and material suppliers). Such application shall also state the amount of any required retainer related to the application. The Contractor shall certify such application for Payment as true and correct. In addition, such Application for Payment shall contain the Contractor's certification that the Contractor has paid all due and payable bills for the Work to date or that the Contractor shall pay the same from the proceeds of such application.
- B. Such applications may include requests for payment for changes properly authorized by Construction Change Directives but not yet included in Change Orders.
- C. Such applications shall not include requests for payment of amounts the Contractor does not intend to pay to a Subcontractor or material supplier because of a dispute or other reason.
- D. Unless otherwise provided in the Contract Documents, the City shall make payments on account of materials and equipment delivered and suitably stored at the site for subsequent incorporation in the Work. If approved in advance by the City, the City shall similarly make payment for materials and equipment suitably stored off the site at a location the parties have agreed upon in writing. The City conditions any such Payment for materials and equipment stored on or off the site upon the Contractor's compliance with measures and actions satisfactory to the City to establish the City's title to such materials and equipment or otherwise protect the City's interest. Such procedures, measures and actions shall include applicable Insurance, storage and transportation to the site for such materials and equipment stored off the site.
- E. The Contractor warrants that title to all Work covered by an Application for Payment shall pass to the City no later than the time of payment. The Contractor further warrants that upon submittal of an Application for Payment, all Work for which Certificates for Payment have been previously issued and payments received from the City shall be free and clear of liens, Claims, security interests or encumbrances in favor of the Contractor,

Subcontractors, material suppliers, or other persons or entities making a Claim by reason of having provided labor, materials and equipment relating to the Work.

**XLIX. CERTIFICATES FOR PAYMENT**

- A. The Architect may issue a certificate for Payment to the City, with a copy to the Contractor, for such amount as the Architect determines is properly due. Otherwise, the Architect shall notify the Contractor and City in writing of the Architect's reasons for withholding certification in whole or in part as provided in Subparagraph L(A). The Architect shall take one or the other action within seven days after receipt of the Contractor's Application for Payment.
- B. The issuance of a Certificate for Payment shall constitute the Architect's representation to the City (based on the Architect's observations at the site and the data comprising the Application for Payment) that the Work has progressed to the point indicated and that the quality of the Work complies with the Contract Documents. The foregoing representations are subject to: the Architect's evaluation of the Work for conformance with the Contract Documents upon Substantial Completion; results of subsequent tests and inspections; minor deviations correctable prior to completion; and specific qualifications expressed in writing by the Architect. The Architect's issuance of a certificate for Payment shall further constitute the Architect's representation that the Contractor is entitled to payment in the amount certified. However, the issuance of a Certificate for Payment shall not be a representation that the Architect has:
  - 1. Made exhaustive or continuous on-site inspections to check the quality or quantity of the Work;
  - 2. Reviewed construction means, methods, techniques, sequences or procedures;
  - 3. Reviewed copies of requisitions received from Subcontractors and material suppliers and other data requested by the City to substantiate the Contractor's right to payment; or
  - 4. Made examination to ascertain how or for what purpose the Contractor has used money previously paid on account of the Contract Sum.

**L. DECISIONS TO WITHHOLD CERTIFICATION**

- A. The Architect may decide not to certify payment and may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect the City. The Architect may do so when (in the Architect's opinion) the Architect can not make the representations to the City required by Subparagraph XLIX(B). If the Architect is unable to certify payment in the amount of the Application, the Architect shall notify the Contractor and City as provided in Subparagraph XLIX(A). If the Contractor and Architect cannot agree on a

revised amount, the Architect shall promptly issue a Certificate for Payment for any amount the Architect is able to certify. The Architect may nullify any Certificate for Payment previously issued in whole or in part based on subsequently discovered evidence or subsequent observations. The Architect may also nullify or deny certification in whole or in part as may be necessary in the Architect's opinion to protect the City from loss because of:

1. Defective Work not remedied;
2. Third party Claims filed or reasonable evidence indicating probable filing of such Claims;
3. Failure of the Contractor to make payments properly to Subcontractors or for labor, materials or equipment;
4. Reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Sum;
5. Damage to the City or another party related to the Work;
6. Reasonable evidence that the Work shall not be completed within the Contract Time, and that the unpaid balance would not be adequate to cover actual or liquidated damages; for the anticipated delay; or
7. Persistent failure to carry out the Work in accordance with the Contract Documents.

- B. When the Contractor causes removal of the above reasons for withholding certification, the Architect shall make such certification for amounts previously withheld.
- C. Regardless of any dispute related to any Certificate of Payment, the Contractor shall expeditiously continue to prosecute the Work.

---

#### **LI. PROGRESS PAYMENTS**

- A. After the Architect has issued a Certificate for Payment, the City shall make payment in the manner and within the time provided in the Contract Documents. The City shall notify the Architect of such payment.
- B. The Contractor shall promptly upon receipt of payment from the City for certified work completed by Subcontractors pay the amount to which said Subcontractor is entitled for such certified portion of the Work, less any percentage portion of the Contractor's retainer applicable to the Subcontractor's work. The Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payments to Sub-subcontractors in similar manner.
- C. The Architect shall, upon request, furnish to a

Subcontractor, if practicable, information regarding percentages of completion or amounts the Contractor has applied for and the City's and Architect's actions thereon related to such subcontractor's work.

- D. Neither the City nor Architect shall have an obligation to pay or to see to the payment of money to a Subcontractor.
- E. If practicable, the City may make Payment to material suppliers as provided for Progress Payments in Paragraphs LI(B-D).
- F. A Certificate for Payment, a progress payment, or the City's partial or complete use or occupancy of the Project shall not constitute acceptance of Work.

---

#### **LII. FAILURE OF PAYMENT.**

The City shall have seven days from the date the City receives a Certificate of Payment to pay the Contractor. If the City does not pay the Contractor the certified amount within such time, the Contractor may notify the City and Architect in writing that the Contractor will stop the Work until the City makes the required payment. Such notice shall provide at least fourteen additional days after receipt for the City to make payment prior to the Contractor stopping the Work. Upon such Work stoppage, the City and Contractor shall extend the Contract Time accordingly and increase the Contract Sum by the Contractor's reasonable costs of shut-down, delay and start-up. The parties shall complete such changes as provided in Changes In The Work, Paragraphs XLI-XLII.

---

#### **LIII. SUBSTANTIAL COMPLETION**

- A. When the Contractor considers that the Work (or a portion thereof that the City agrees to accept separately) is substantially complete, the Contractor shall prepare and submit to the Architect a comprehensive list of items to be completed or corrected. The Contractor shall proceed promptly to complete and correct items on the list. Failure to include an item on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. Upon receipt of the Contractor's list, the Architect shall make an inspection to determine whether the Work or designated portion thereof is substantially complete. If the Architect's inspection discloses any item that does not comply with the Contract Documents (including any items on the Contractor's list) the Contractor shall complete or correct such item upon the Architect's written notification. Once corrected or completed, the Contractor may submit a request to the Architect for another inspection to determine Substantial Completion.
- B. When the Work or designated portion thereof is substantially complete, the Architect may prepare a Certificate of Substantial Completion. Upon the City's approval, such Certificate shall establish: (1) the date of Substantial Completion; (2)

responsibilities of the Contractor for security, maintenance, heat, utilities, damage to the Work and Insurance; and (3) the time for the Contractor to finish all items on the list accompanying the Certificate. Warranties provided in the Contract Documents shall commence on the date of Substantial Completion unless otherwise provided in the Certificate of Substantial Completion. The Contractor shall accept the Certificate of Substantial Completion and the responsibilities assigned in such certificate by signing the same. The Architect shall submit the Certificate to the Contractor for such acceptance.

- C. The City shall make payment for the Work as certified in the Certificate of Substantial Completion upon the Contractor's written application and the Architect's Certificate for payment as provided in the Contract Documents.
- D. The Contractor shall secure and deliver to the City any written warranties and guarantees from Subcontractors, Sub-Subcontractors and suppliers. Such warranties and guarantees shall state the period of warranty as required by the Contract Documents or otherwise as the City has agreed. The Contractor warrants all of the Work regardless of separate warranties by Subcontractors at any tier.

---

**LIV. PARTIAL OCCUPANCY OR USE**

- A. The City may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor. Such partial occupancy or use may commence whether or not the portion is substantially complete. Prior to any partial occupancy or use, the City and Contractor shall by separate written agreement provide for the responsibilities assigned to each of them for at least the following: payments, retainer, security, maintenance, heat, utilities, damage to the Work and Insurance. Such written agreement shall also include terms concerning the period for correction of the Work and commencement of warranties. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Architect as provided under Subparagraph LIII(A). The Contractor shall not unreasonably withhold consent to any such partial occupancy or use. The City and Contractor shall determine the stage of the progress of the Work by written agreement.
- B. Immediately prior to such partial occupancy or use, the

City, Contractor and Architect shall jointly inspect the subject area. The parties shall use such inspection to determine and record the condition of the Work.

- C. Unless the City and the Contractor agree otherwise in writing, the City's partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of such Work.

---

**LV. FINAL COMPLETION AND FINAL PAYMENT**

- A. Upon receipt of written notice that the Work is ready for final inspection and acceptance and upon receipt of a final Application for Payment, the Architect shall promptly make such inspection. If the Architect finds the Work acceptable under the Contract Documents and the Contract fully performed, the Architect shall promptly issue a final Certificate for Payment stating that the Work has been completed in accordance with terms and conditions of the Contract Documents. Such final Certificate shall mean the entire balance found to be due the Contractor and noted in said final Certificate is due and payable.
- B. The Architect's final Certificate for Payment shall constitute a further representation that the Contractor has fulfilled the conditions listed in Subparagraph LV(C).
- C. Neither final payment nor any remaining retained percentage shall become due until the Contractor submits to the Architect: (1) an affidavit that payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the City or the City's property might be responsible or encumbered (less amounts withheld by City) have been paid or otherwise satisfied, (2) a Certificate evidencing that Insurance required by the Contract Documents to remain in force after final payment is currently in effect and shall not be canceled or allowed to expire unless the insurer or Contractor provides at least 30 days' prior written notice to the City, (3) a written statement that the Contractor knows of no reason that the Insurance shall not be renewable to cover the period required by the Contract Documents, (4) consent of surety, if any, to final payment and (5), if required by the City, other data establishing payment or satisfaction of obligations, such as receipts, releases and waivers of liens, Claims, security interests or encumbrances arising out of the Contract as may be designated by the City.
- D. After Substantial Completion, if final completion of the Work is materially delayed through no fault of the Contractor or by Change Orders affecting final completion, the Contractor may apply in writing for the City to make payment of the balance due for that portion of the Work fully completed and accepted as certified by the Architect. Such application, certification and payment shall not terminate the contract. If the remaining balance for Work not fully completed or corrected is less than any retainer

stipulated in the Contract Documents, the Contractor shall submit the written consent of surety to payment of the balance due for that portion of the Work fully completed and accepted to the Architect prior to certification of such payment. Such payment shall be made under terms and conditions governing final payment, except that it shall not constitute a waiver of Claims. As to such portion, the making of final payment shall constitute a waiver of Claims by the City as provided in Subparagraph XXXVII(C).

- E. When the Contractor, any Subcontractor or any material supplier accepts final payment, such acceptance shall constitute a waiver of Claims by that payee except those previously made in writing and identified by that payee as unsettled at the time of final Application for Payment. Such payee shall make such waiver in addition to the waiver described in Subparagraph XXXVII(C).

## **SAFETY**

### **LVII. SAFETY PRECAUTIONS AND PROGRAMS**

- A. The Contractor shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work.
- B. The Contractor shall immediately notify the City and Architect in writing whenever the Contractor encounters material on the site that the Contractor reasonably believes to be asbestos or polychlorinated biphenyl (PCB).

### **LVIII. SAFETY OF PERSONS AND PROPERTY**

- A. The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury or loss to:
1. Employees on the Work and other persons who may be affected thereby;
  2. The Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody or control of the Contractor or the Contractor's Subcontractors or Sub-subcontractors; and
  3. Other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction.

- B. The Contractor shall give notices and comply with applicable laws, ordinances, rules, regulations and lawful orders of public authorities bearing on safety of persons or property or their protection from damage, injury or loss.
- C. The Contractor shall erect and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection, including posting danger signs and other warnings against hazards, promulgating safety regulations and notifying owners and users of adjacent sites and utilities. The Contractor shall take all reasonable and proper precautions to protect persons, animals, and vehicles from injury. The Contractor shall leave fire hydrants and inlets free from encumbrance.
- D. The Contractor shall exercise utmost care when conducting potentially dangerous activities related to the work, including: the use or storage of explosives or other hazardous materials; or the use or storage of potentially dangerous equipment. The Contractor shall conduct such activities only under the supervision of properly qualified personnel.
- E. The Contractor shall promptly remedy damage and loss (other than damage or loss insured under property Insurance required by the Contract Documents) to property referred to in Clauses LVII(A)(2) and LVII(A)(3) caused in whole or in part by the Contractor, a Subcontractor, a Sub-subcontractor, or anyone directly or indirectly employed by any of them, or by anyone for whose acts they may be liable and for which the Contractor is responsible under Clauses LVII(A)(2) and LVII(A)(3), except damage or loss attributable to acts or omissions of the City or Architect or anyone directly or indirectly employed by either of them, or by anyone for whose acts either of them may be liable, and not attributable to the fault or negligence of the Contractor. The foregoing obligations of the Contractor are in addition to the Contractor's obligations under Paragraph XXXI, Indemnification.
- F. The Contractor shall designate a responsible member of the Contractor's organization at the site whose duty shall be the prevention of accidents. This person shall be the Contractor's superintendent unless otherwise designated by the Contractor in writing to the City and Architect.
- G. The Contractor shall not load or permit any part of the construction or site to be loaded so as to endanger its safety.
- H. The Contractor shall provide sanitary Latrines for the Contractor's work force and other persons related to the Work on the Work site. The, type, number and location for such latrine facilities shall be subject to approval by the City.



**LVIII. EMERGENCIES**

In an emergency affecting safety of persons or property, the Contractor shall act to prevent threatened damage, injury or loss. Additional compensation or extension of time Claimed by the Contractor on account of an emergency shall be determined as provided in Paragraph XXXVII, Claims and Disputes and Paragraphs XLI--XLII, Changes In The Work.

**FINANCIAL SECURITY****LIX. CONTRACTOR'S LIABILITY INSURANCE**

A. The Contractor shall purchase such Insurance as shall protect the Contractor and the City from Claims set forth below which may arise out of or result from the Contractor's operations under the Contract. Such operations shall include operations by the Contractor or by a Subcontractor or by anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable. Such claims shall include the following:

1. Claims under workers' compensation, disability benefit and other similar applicable employee benefit acts;
2. Claims for damages because of bodily injury, occupational sickness or disease, or death of the Contractor's employees;
3. Claims for damages because of bodily injury, sickness or disease, or death of any person other than the Contractor's employees;
4. Claims for damages insured by usual personal injury liability coverage which are sustained (1) by a person as a result of an offense directly or indirectly related to employment of such person by the Contractor, or (2) by another person;
5. Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property, including loss of use resulting therefrom;
6. Claims for damages because of bodily injury, death of a person or property damage arising out of ownership, maintenance or use of a motor vehicle; and
7. Claims involving contractual liability Insurance applicable to the Contractor's obligations under Paragraph XXXI, Indemnification.

- B. The Contractor shall procure the Insurance required by Subparagraph (A) of this paragraph in the minimum amounts (applicable law or a special condition of the Contract Documents may require greater coverage) as follows:

**Worker's Comp**

State	Statutory
Federal	Statutory

**Auto Liability**

Bodily Injury & Property Damage	\$1,000,000
	Combined Single Limit.

**Commercial General Liability**

Bodily Injury & Property Damage	\$1,000,000
	each occurrence
Aggregate	\$2,000,000
Personal Injury	\$1,000,000
	each occurrence
Contractual Liability	\$1,000,000
	each occurrence
Products and Completed Operations	\$1,000,000
	each occurrence

- C. All Liability Insurance Policies shall provide coverage: (1) on an "occurrence basis" only; (2) by endorsement to add the City of Lincoln, its officials, employees and volunteers as "Additional Insured;" and (3) without interruption from the Work Commencement Date until the date of final payment (as provided in the Contract Documents) or other coverage termination date for any coverage the Contractor is required to maintain after such final payment.
- D. The Contractor shall obtain all Insurance coverage with insurers authorized to do business in the State of Nebraska. The Contractor shall obtain all Insurance coverage with an insurer that has an A.M. Best's Rating of not less than A:VII, unless the City approves otherwise in writing.
- E. The Contractor shall not commence work under this Contract until the Contractor has obtained all Insurance required by the Contract Documents and the City Attorney has approved such Insurance for compliance with the Contract Documents. The Contractor shall not allow any Subcontractor to commence work on any subcontract until the Subcontractor has likewise obtained all similar Insurance required of the Subcontractor.

- F. The Contractor shall file all Certificates of Insurance with the Risk Management Office of the City of Lincoln on the standard ACORD CERTIFICATE OF INSURANCE form showing the specific limits of Insurance coverage required and any deductibles required. Such Certificate shall specifically state the Insurance policies are endorsed to require the insurer to provide the City of Lincoln 30 days' notice of cancellation, failure to renew or any material reduction of Insurance coverage. If any of the foregoing Insurance coverage is required to remain in force after final payment and is reasonably available, the Contractor shall submit an additional Certificate evidencing continuation of such coverage with the final Application for Payment as required by Subparagraph LV(C). The Contractor shall immediately notify the City of any material reduction or other changes related to any required coverage.

#### **LX. PROPERTY INSURANCE**

- A. Where buildings or structures are to be constructed under this Contract, the Contractor shall provide and maintain "all risk" property Insurance provided on a "completed value" basis, covering such building or structure to 100% of the insurable value thereof. Such Insurance shall contain a "waiver of occupancy" endorsement. The insurer shall pay losses, if any, to the City of Lincoln and Contractor as their interest may appear. The Contractor shall file a Certificate of Insurance evidencing such Insurance coverage with the Risk Management Office of the City of Lincoln as soon as any such building or structure becomes insurable until title for such building or structure passes to the City. Such Certificate shall show that the City Attorney has approved such Insurance as represented on the Certificate for compliance with the Contract Documents. See Also: Contractor's obligations and assumption of risk in Subparagraph XXV.
- B. Waivers of Subrogation. The City and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents and employees, each of the other, and (2) the Architect, Architect's consultants, separate contractors, if any, and any of their subcontractors, sub-subcontractors, agents and employees, for damages caused by fire or other perils to the extent covered by property Insurance obtained pursuant to this Paragraph LX or other property Insurance applicable to the Work, except such rights as they have to proceeds of such Insurance held by the City as fiduciary. The City or Contractor, as appropriate, shall require of the Architect, Architect's consultants, separate contractors, if any, and the subcontractor, sub-subcontractors, agents and employees of any of them, by appropriate agreements, written where legally required for validity, similar waivers

each in favor of other parties enumerated herein. The policies shall provide such waivers of Subrogation by endorsement or otherwise. A waiver of Subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the Insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged.

#### **LXI. PERFORMANCE BOND AND PAYMENT BOND**

- A. Within ten days after the acceptance of the bid, the Contractor shall furnish, on forms provided by the City, construction performance and construction payment Bonds, in a sum not less than the Contract Sum, executed by the Contractor and by a corporate surety company authorized to transact business in the State of Nebraska. Such Bonds shall be conditioned upon the faithful performance of all the terms and conditions of the Contract Documents, including the holding harmless of the City from failure to do so, and including the making good of any and all guarantees that the Contract Documents may require and the construction payment Bonds shall be further conditioned upon the payment of all laborers and material suppliers used in the performance of the Contract, including Insurance premiums and interest.

### **TESTING AND CORRECTING WORK**

#### **LXII. TESTS AND INSPECTIONS**

- A. The Contractor shall conduct or arrange for any tests, inspections and approvals of portions of the Work required by the Contract Documents or by laws, ordinances, rules, regulations or orders of public authorities having jurisdiction at appropriate times. Unless otherwise provided, the Contractor shall make arrangements for such tests, inspections and approvals with an independent testing laboratory or entity acceptable to the City, or with the appropriate public authority, and shall bear all related costs of tests, inspections and approvals. The City shall bear costs of tests, inspections or approvals that do not become requirements until after bids are received or negotiations concluded.
- B. If the Architect, City or public authorities having jurisdiction determine that portions of the Work require additional testing, inspection or approval not included under Subparagraph LXII(A), the City shall instruct the Contractor to make arrangements for such additional testing, inspection or approval by an entity acceptable to the City. The City shall bear such costs except as provided in Subparagraph LXII(C).
- C. If such procedures for testing, inspection or approval under Subparagraphs LXII(A-B) reveal failure of the portions of the Work

to comply with requirements established by the Contract Documents, the Contractor shall bear all costs made necessary by such failure including those of repeated procedures and compensation for the Architect's services and expenses.

- D. The Contractor shall secure all required Certificates of testing, inspection or approval unless the Contract Documents require otherwise. The Contractor shall promptly deliver such Certificates to the Architect.
- E. The Contractor shall furnish, at no expense to the City, such samples of materials as may be required by the Architect or the City for testing. The Contractor shall bear any expense for retesting, required to establish the quality or acceptability of the materials in question.
- F. The Contractor shall not install material of any kind in the project until the Architect has inspected and approved such materials.
- G. The City reserves the right to retest all materials, prior to incorporation into the work, at the City's expense. The City may then reject all materials that, when retested, do not comply with the Contract Documents.
- H. The Contractor shall conduct or arrange for tests or inspections conducted pursuant to the Contract Documents promptly to avoid unreasonable delay in the Work.

#### **LXIII. UNCOVERING OF WORK**

- A. If a portion of the Work is covered contrary to the Architect's request or to requirements specifically expressed in the Contract Documents, the Contractor shall uncover the same for the Architect's observation upon the written request of the Architect. The Contractor shall replace or restore such uncovered Work at the Contractor's expense without any adjustment to the Contract Time.
- B. If a portion of the Work has been covered that the Architect has not specifically requested to observe prior to its being covered, the Architect may request to see such Work. Such request shall be in writing and approved by the City. Upon such request, the Contractor shall uncover the specified Work. If such Work is not in accordance with the Contract Documents, the Contractor shall pay such costs unless the condition was caused by the City. If such Work is in accordance with the Contract Documents, the City shall pay such costs.

#### **LXIV. CORRECTION OF WORK**

- A. The Contractor shall promptly correct Work rejected by the Architect or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed. The Contractor shall bear costs of correcting such rejected Work, including additional testing and inspections and compensation for the Architect's services and expenses made necessary thereby.
- B. Unless specified otherwise in the terms of an applicable special warranty required by the Contract Documents, the Contractor shall warrant the work for a period of one year after: Substantial Completion of the Work or a designated portion thereof; or the date of commencement of warranties established under Subparagraph LIV(A). During such warranty period, if the City discovers that any of the Work is not in accordance with the Contract Documents, the City shall notify the Contractor in writing. The City shall give such notice promptly after discovery of the condition. Upon such notice, the Contractor shall promptly correct the work, at the Contractor's expense, unless the City has previously given the Contractor a written acceptance of such condition. The Contractor shall extend the warranty period for any portions of Work first performed after Substantial Completion. The Contractor shall extend the warranty period for the number of days between Substantial Completion and the actual completion of such Work. All obligations under this Subparagraph LXIV(B) shall survive acceptance of the Work under the Contract and termination of the Contract.
- C. The Contractor shall remove from the site portions of the Work that are not in accordance with the requirements of the Contract Documents and are not corrected by the Contractor nor accepted by the City.
- D. If the Contractor fails to correct non-conforming Work within a reasonable time, the City may correct it in accordance with Paragraph IX. If the Contractor does not proceed with correction of such non-conforming Work within a reasonable time fixed by written notice from the Architect, the City may remove it and store the salvageable materials or equipment at the Contractor's expense. If the Contractor does not pay costs of such removal and storage within ten days after written notice the City may upon ten additional days' written notice sell such materials and equipment at auction or at private sale and shall account for the proceeds thereof, after deducting costs and damages owed by the Contractor, including compensation for the Architect's services and expenses made necessary thereby. If such proceeds of sale do not cover costs owed by the Contractor, the City shall automatically reduce the Contract Sum by the deficiency. If payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor shall pay the difference to the City.

E. The Contractor shall bear the cost of correcting destroyed or damaged construction, whether completed or partially completed, of the City or separate contractors caused by the Contractor's correction or removal of Work that is not in accordance with the requirements of the Contract Documents.

F. Nothing contained in this Paragraph LXIV shall establish a period of limitation with respect to other obligations that the Contractor might have under the Contract Documents. The one year warranty period as described in Subparagraph LXIV(B) relates only to the specific obligation of the Contractor to correct the Work and has no relationship to the time within which the City may enforce the Contractor's obligation to comply with the Contract Documents, nor to the time within which the City may commence proceedings to establish the Contractor's liability other than specifically to correct the Work.

#### **LXV. ACCEPTANCE OF NON-CONFORMING WORK**

If the City elects in writing to accept Work that is not in accordance with the requirements of the Contract Documents, the City may do so instead of requiring its removal and correction. Upon such election, the City and Contractor shall reduce the Contract Sum as appropriate and equitable. The City and Contractor shall make such adjustment whether or not the City has made final payment under the Contract Documents. The Contractor shall pay the difference, if any, to the City within 10 days from such adjustment.

## **MISCELLANEOUS TERMS**

#### **LXVI. GOVERNING LAW**

The Contract shall be governed by the laws of the State of Nebraska.

#### **LXVII. SUCCESSORS AND ASSIGNS**

The City and Contractor respectively bind themselves, their partners, successors, assigns and legal representatives to the other party hereto as to covenants, agreements and obligations contained in the Contract Documents. Neither party to the Contract shall assign or delegate the Contract as a whole without written consent of the other. If either party attempts to make such an assignment or delegation without such consent, that party shall nevertheless remain legally responsible for all obligations under the Contract.

#### **LXVIII. WRITTEN NOTICE**

The City, Contractor or Architect may deliver written notice in person to the individual; to a member of the firm or entity; or to an officer of the corporation for which it was intended. Written notice may be delivered by registered or certified mail to the last business address known to the party giving notice. Delivery by either method is hereby acknowledged as sufficient and adequate service of any written notice related to the Contract.

#### **LXIX. RIGHTS AND REMEDIES**

- A. Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to duties, obligations, rights and remedies otherwise imposed or available by law.
- B. No action or failure to act by the City, Architect or Contractor shall constitute a waiver of a right or duty afforded them under the Contract, nor shall such action or failure to act constitute approval of or acquiescence in a breach thereunder, except as may be specifically agreed in writing.

#### **LXX. COMMENCEMENT OF STATUTORY LIMITATION PERIOD**

- A. Before Substantial Completion. As to acts or failures to act occurring prior to the relevant date of Substantial Completion, any applicable statute of limitations shall commence to run and any alleged cause of action shall be deemed to have accrued in any and all events not later than such date of Substantial Completion;
- B. Between Substantial Completion and Final Certificate for Payment. As to acts or failures to act occurring subsequent to the relevant date of Substantial Completion and prior to issuance of the final Certificate for Payment, any applicable statute of limitations shall commence to run and any alleged cause of action shall be deemed to have accrued in any and all events not later than the date of issuance of the final Certificate for Payment; and
- C. After Final Certificate for Payment. As to acts or failures to act occurring after the relevant date of issuance of the final certificate for Payment, any applicable statute of limitations shall commence to run and any alleged cause of action shall be deemed to have accrued in any and all events not later than the date of any act or failure to act by the Contractor pursuant to any warranty provided under Paragraph XVII, the date of any correction of the Work or failure to correct the Work by the Contractor under Paragraph LXIV, or the date of actual commission of any other act or failure to perform any duty or obligation by the Contractor or City, whichever occurs last.

D. Notwithstanding any provision herein to the contrary, no applicable statute of limitations shall commence for any portion of the Work that is not in accordance with the requirements of the Contract Documents, that would not be visible or apparent upon conducting a reasonable investigation, and that is not discovered by the City until after the date that would otherwise be the date of commencement of the applicable statute of limitations. In such case, the applicable statute of limitations shall commence on the date of such discovery by the City.

---

**LXXI. INDEPENDENT CONTRACTOR**

The City is interested only in the results obtained and Contractor shall perform as an independent contractor with the sole control of the manner and means of performing the Work required under the Contract. Contractor shall complete the Contract according to its own means and methods of work, which shall be in the exclusive charge and control of Contractor, and which shall not be subject to control or supervision by the City except as to the results of the Work. Contractor is, for all purposes arising out of the Contract, an independent contractor, and the Contractor or any Subcontractor, agent, employee or representative and employees or agents of any of them shall not be deemed an employee of the City. It is expressly understood and agreed that Contractor shall in no manner be entitled to any benefits to which the City's employees are entitled including, but not limited to, overtime, any retirement benefits, workers' compensation benefits and injury leave, or other benefits.

## TERMINATION OR SUSPENSION

---

**LXXII. TERMINATION BY THE CONTRACTOR**

A. The Contractor may terminate the Contract if the Work is stopped for a period of 30 days through no act or fault of the Contractor or a Subcontractor, Sub-subcontractor or their agents or employees or any other persons performing portions of the Work under contract with the Contractor, for any of the following reasons:

1. Issuance of an order of a court or other public authority having jurisdiction;
2. An act of government, such as a declaration of national emergency, making material unavailable;
3. The failure of the Architect to issue a certificate for Payment when the Architect has not notified the Contractor of the reason for withholding certification as provided in Subparagraph XLIX(A), or the failure of

the City to make payment on a Certificate for Payment within the time stated in the Contract Documents; or

4. The City's repeated suspensions, delays or interruptions as described in Paragraph LXXIV constitute in the aggregate more than 100 percent of the total number of days scheduled for completion or 120 days in any 365-day period, whichever is less.

B. If one of the above reasons exist; the Contractor may upon seven additional days' written notice to the City and Architect, terminate the Contract and recover from the City payment for Work executed and for proven loss with respect to materials, equipment, tools, and construction equipment and machinery, including reasonable overhead, profit and damages.

C. If the City has persistently failed to fulfill obligations important to the progress of the Work under the Contract Documents, causing the Contractor to stop the Work for a period of 60 days through no act or fault of the Contractor (or a Subcontractor or their agents or any other persons performing portions of the Work under the contract with the Contractor) the Contractor may, upon seven additional days' written notice to the City and the Architect, terminate the Contract and recover from the City as provided in Subparagraph LXXII(B)

---

**LXXIII. TERMINATION BY THE CITY FOR CAUSE**

A. The City may terminate the Contract if the Contractor:

1. Refuses or fails to supply enough properly skilled workers or proper materials;
2. Fails to make payment to Subcontractors for materials or labor in accordance with the respective agreements between the Contractor and the Subcontractors;
3. Disregards laws, ordinances, or rules, regulations or orders of a public authority having jurisdiction; or
4. Otherwise commits a substantial breach of any provision of the Contract Documents.

B. When any of the above reasons exist, the City may without prejudice to any other rights or remedies of the City may (after giving the Contractor and the Contractor's surety, if any, seven days' written notice) terminate employment of the Contractor. In addition the City may (subject to any prior rights of the surety):

1. Take possession of the site and of all materials, equipment, tools, and construction equipment and machinery thereon owned by the Contractor;
2. Accept assignment of subcontracts pursuant to Paragraph XL; and
3. Finish the Work by whatever reasonable method the City may deem expedient.

- C. When the City terminates the Contract for one of the reasons stated in Subparagraph LXXIII(A), the Contractor shall not receive further payment until the Work is finished.
- D. If the unpaid balance of the Contract Sum exceeds the costs of finishing the Work, (including compensation for the Architect's services and expenses made necessary thereby) such excess shall be paid to the Contractor. If such costs exceed the unpaid balance, the Contractor shall pay the difference to the City. The Architect shall certify any amount to be paid to the Contractor or City upon application, and this obligation for payment shall survive termination of the Contract.

---

**LXXIV. SUSPENSION BY THE CITY FOR CONVENIENCE**

- A. The City may, without cause, order the Contractor in writing to suspend, delay or interrupt the Work in whole or in part for such period of time as the City may determine.
- B. The City and Contractor shall make an adjustment for increases in the cost of the Contract caused by suspension, delay or interruption. Such adjustment shall include a reasonable profit on the increased cost. No adjustment shall be made to the extent that:
1. Performance is, was or would have been so suspended, delayed or interrupted by another cause for which the Contractor is responsible; or
  2. An equitable adjustment is made or denied under another provision of this Contract.
- C. Adjustments made in the cost of performance may have a mutually agreed fixed or percentage fee.

---

**LXXV. TERMINATION BY THE CITY FOR CONVENIENCE**

- A. The City may at its option, terminate this Contract in whole or in part at any time without cause by written notice thereof to the Contractor.
- B. Upon any such termination, the Contractor agrees to waive any claims for damages, including loss of anticipated profits, on account thereof, and as the sole right and remedy of the Contractor, the City shall pay Contractor in accordance with this Paragraph. The provisions of the Contract which by their nature survive final acceptance of the Work, shall remain in full force and effect after such termination to the extent provided in such provisions.

- C. Upon receipt of any such notice of termination, the Contractor shall, unless the Notice directs otherwise, immediately:
1. Discontinue the Work to the extent specified by the City
  2. Place no further orders or subcontracts for materials, equipment, services or facilities, except as may be necessary for completion of that portion of the Work, if any, the City has directed not to be discontinued;
  3. Promptly make every reasonable effort to procure cancellation upon satisfactory terms as determined by the City of all orders and subcontracts not related to that portion of the Work, if any, the City has directed not to be discontinued;
  4. Do only such other activity as may be necessary to preserve and protect work already in progress and to protect materials and plants and equipment on the Project Site or in transit thereto.
- D. Upon such termination, the obligations of the Contract shall continue as to portions of the Work already performed and as to bona fide obligations the Contractor assumed prior to the date of termination.
- E. Upon termination, the City shall pay the Contractor the full cost of all Work properly done by the Contractor to the date of termination not previously paid for by the City. If at the date of such termination the Contractor has properly prepared or fabricated off site any goods for subsequent incorporation in the Work, the City may direct the Contractor to deliver such goods to the Site or to such other place as the City may reasonably determine, whereupon the City shall pay to the Contractor the cost for such goods and materials.

Asbestos 5, 22  
Bond 5, 16, 17, 24  
Certificate 6, 8, 12, 14, 18, 19, 20, 21, 23, 24, 25, 27, 28  
Change Order 1, 5, 9, 13, 14, 16, 17, 18, 21  
Claim 1, 4, 5, 8, 10, 11, 12, 13, 17, 18, 19, 21, 22, 23, 29  
Construction Change Directive 1, 16, 18  
Contract Sum 1, 4, 6, 7, 8, 9, 10, 11, 13, 14, 16, 17, 18, 19, 24, 26, 28  
Contract Time 1, 4, 6, 13, 16, 17, 19, 25  
Correct 4, 5, 6, 7, 8, 12, 18, 20, 21, 25, 26, 27  
Cross References  
    02-CONSTRUCTION, AND INTENT  
        II(G) 1  
    04-GENERAL PRECONDITIONS AND ASSURANCES  
        IV 4  
    09-CITY'S RIGHT TO CARRY OUT THE WORK  
        IX 26  
    14-REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR  
        XIV 12  
        XIV(A) 8  
        XIV(D) 1  
    17-WARRANTY  
        XVII 12, 27  
    18-PERMITS, FEES AND NOTICES  
        XVIII 5  
        XVIII(C) 7  
    20-ALLOWANCES  
        XX(B)(2) 9  
    24-SHOP DRAWINGS, PRODUCT DATA AND SAMPLES  
        XXIV 7, 12  
        XXIV(A) 1  
    25-USE OF SITE  
        XXV 11, 24  
    31-INDEMNIFICATION  
        XXXI 11, 22, 23  
    37-CLAIMS AND DISPUTES  
        XXXVII 17, 21, 22  
        XXXVII(C) 21  
    39-AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK  
        XXXIX(A) 14  
    40-CONTINGENT ASSIGNMENT OF SUBCONTRACTS  
        XL 28  
    41-CHANGES  
        XLI 16, 19, 22  
    42-CONSTRUCTION CHANGE DIRECTIVES  
        XLII 16, 19, 22  
        XLII(E) 16  
    49-CERTIFICATES FOR PAYMENT  
        XLIX(A) 19, 28  
        XLIX(B) 19  
    50-DECISIONS TO WITHHOLD CERTIFICATION  
        L(A) 18  
    51-PROGRESS PAYMENTS  
        LI(B-D) 19  
    53-SUBSTANTIAL COMPLETION  
        LIII 2

LIII(A) 20  
 54-PARTIAL OCCUPANCY OR USE  
 LIV(A) 25  
 55-FINAL COMPLETION AND FINAL PAYMENT  
 LV(C) 20, 23  
 57-SAFETY OF PERSONS AND PROPERTY  
 LVII(A)(2) 22  
 LVII(A)(3) 22  
 58-EMERGENCIES  
 LVIII 13  
 59-CONTRACTOR'S LIABILITY INSURANCE  
 LIX 17  
 60-PROPERTY INSURANCE  
 LX 17, 24  
 61-PERFORMANCE BOND AND PAYMENT BOND  
 LXI 17  
 62-TESTS AND INSPECTIONS  
 LXII(A) 25  
 LXII(A-B) 12, 25  
 LXII(C) 25  
 64-CORRECTION OF WORK  
 LXIV 12, 26, 27  
 LXIV(B) 25, 26  
 72-TERMINATION BY THE CONTRACTOR  
 LXXII(B) 28  
 73-TERMINATION BY THE CITY FOR CAUSE  
 LXXIII 15  
 LXXIII(A) 28  
 74-SUSPENSION BY THE CITY FOR CONVENIENCE  
 LXXIV 28  
 Default 5, 18  
 Drawings 1, 2, 3, 6, 7, 9, 12  
 Hold harmless 10, 11, 24  
 Inspect 4, 5, 6, 7, 8, 12, 18, 19, 20, 25  
 Insurance 5, 14, 16, 17, 18, 20, 21, 22, 23, 24  
 Liquidated Damages 1, 17, 19  
 Modification 1, 5, 6, 8, 9  
 Notice 5, 7, 8, 13, 17, 19, 20, 21, 22, 23, 25, 26, 27, 28, 29  
 Opinion 13, 18, 19  
 Polychlorinated biphenyl 22  
 Subrogation 24  
 Substantial Completion 1, 2, 12, 17, 18, 20, 21, 25, 27  
 Supplier 2, 3, 12, 18, 19, 20, 21, 24  
 Test 5, 7, 12, 18, 25  
 Utilities 4, 7, 10, 11, 20, 22  
 Utility 5  
 Waive 7, 13, 24, 29  
 Waiver 21, 24, 27